

11/09/2011

Page 1 of 1

1214840 - R8 SDMS



Third West Weekly Report  
Shepherd, Michael

to:

Joyce Ackerman, 'Craig Barnitz (cbarnitz@utah.gov)'

11/09/2011 02:18 PM

Hide Details

From: "Shepherd, Michael" <Michael.Shepherd@PacifiCorp.com>

To: Joyce Ackerman/R8/USEPA/US@EPA, "'Craig Barnitz (cbarnitz@utah.gov)'"  
<cbarnitz@utah.gov>

#### 6 Attachments



Weekly Reports 10-31-11 through 11-04-11.pdf Third West Weekly Log 2011-44.pdf 223514-1.pdf 223662-1.pdf 223762-1.pdf



223763-1.pdf

Joyce & Craig,

Attached are the reports for the week of October 31, 2011.

All air monitoring results came back negative.

No monitoring took place on November, 1, 2011 due to weather. No work was done this day.

Please let me know if you have any questions.

Thanks,

Mike Shepherd  
Project Manager  
Rocky Mountain Power - Major Projects  
801.220.4584 Office  
801.631.1310 Cell  
801.220.2797 Fax  
[michael.shepherd@pacificorp.com](mailto:michael.shepherd@pacificorp.com)



November 9, 2011

Laboratory Code: RES  
Subcontract Number: NA  
Laboratory Report: RES 223762-1  
Project # / P.O. #: None Given  
Project Description: 3rd West Sub Station  
RMP

David Roskelley  
R & R Environmental  
47 West 9000 South #2  
Sandy UT 84070

Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

RES 223762-1 is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,

A handwritten signature in black ink, appearing to read "Jeanne Orr", is written over a horizontal line.

Jeanne Spencer Orr  
President

# RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0; TDH: #30-0015


TABLE I. TEM AIR FILTER SAMPLE DATA AND ANALYTICAL RESULTS

RES Job Number: RES 223762-1  
 Client: R & R Environmental  
 Client Project Number / P.O.: None Given  
 Client Project Description: 3rd West Sub Station RMP  
 Date Samples Received: November 7, 2011  
 Analysis Type: TEM, AHERA  
 Turnaround: 24 Hour  
 Date Samples Analyzed: November 7, 2011

Client ID Number	Lab ID Number	Area Analyzed	Air Volume Sampled	Number of Asbestos Structures Detected	Analytical Sensitivity	Asbestos Concentration	Filter Loading
		(mm <sup>2</sup> )	(L)		(s/cc)	(s/cc)	(s/mm <sup>2</sup> )
3W-110411-E	EM 819882	0.0770	1018	ND	0.0049	BAS	BAS
3W-110411-S	EM 819883	0.1100	241	ND	0.0145	BAS	BAS
3W-110411-N	EM 819884	NA	0	NA	---	---	---
3W-110411-W	EM 819885	0.0880	973	ND	0.0045	BAS	BAS

NA = Not Analyzed  
 ND = None Detected  
 BAS = Below Analytical Sensitivity  
 Average Grid Opening in mm<sup>2</sup> = 0.011

Filter Material = Mixed Cellulose Ester  
 Filter Diameter = 25 mm  
 Effective Filter Area = 385 sq mm

 Digitally  
 signed by Gina  
 Vetroine  
 Date:  
 2011.11.09  
 07:33:03  
 0702

DATA QA



## 3<sup>rd</sup> West Substation Site Project Safety Audit

Project: 3<sup>rd</sup> West Sub Station

Date: 10/31/11

Location: 3<sup>rd</sup> West, 1<sup>st</sup> South, SLC

Job Number: \_\_\_\_\_

Survey Conducted By: Justin Kargis

Title: \_\_\_\_\_

		In Compliance	Out of Compliance	N/A	
Standard	Title	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Corrective Action Taken and Date
1926.59	Hazard Communication Program, List of Chemicals, Training, MSDSs.			x	
1926.500 (b) & (d) (old standard)	Guardrails on open sided floors, floor holes and runways.			x	
1926.404 (b)	Ground fault circuit interrupters or an assured equipment grounding conductor program in use.	x			
1926.451 (b)	The employer shall instruct each employee in the recognition and avoidance of unsafe conditions.			x	
1926.451 (d)	Tubular welded scaffolds shall be properly braced so that they are plumb, square and rigid; legs on plumb, adjustable, mud sills, etc. to support the maximum load; guardrails and toe boards shall be installed.			x	
1926.100 (a)	Head protection, where there is a possible danger of head injury.	x			

<i>Standard</i>	<i>Title</i>	In Compliance	Out of Compliance	N/A	<i>Corrective Action Taken and Date</i>
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.652 (a) (1)	Excavation protective systems; examination by competent person when less than 5 feet in depth.			x	
1926.20 (b) (2)	Employer responsibility to initiate and maintain safety and health programs.	x			
1926.20 (b) (1)	Employer responsibility to provide for frequent and regular inspections by designated competent persons.			x	
1926.451 (e)	Manually propelled scaffolds shall have tight planking for the full width, platforms secured, ladder or stairway provided, suitable footing, stand plumbs, wheels locked, guardrails and toe boards.			x	
1926.1052 (c) (1)	Stair rail and handrail along each unprotected edge.			x	
1926.25 (a)	Debris, scrap lumber with protruding nails, not cleared for work areas, stairs and around structures.			x	
1926.50	First aid shall be available in the absence of an infirmary, or other that is reasonably accessible; first aid supplies shall be accessible and telephone numbers posted.			x	
1926.451 (a) (13)	Scaffolding safe access not provided by ladder or equivalent.			x	
1926.651 (k) (1)	Excavations, protective systems, inspected daily by a competent person and as needed.			x	
1926.403 (b) (2)	Employer shall ensure electrical equipment is free from recognized hazards, is suitable, used in accordance with the listing, labeling or certification.	x			

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.451 (a) (4)	Scaffolding shall have guardrails and toe boards when more than 10 feet high and when less than 45 inches of work space.			x	
1926.405 (g) (2)	Flexible cords shall be used without splice or tap; strain relief shall be provided.			x	
1926.405 (b)	Electrical boxes, fittings shall have covers, faceplates or canopy and holes shall be smooth where cords pass through; and unused openings in cabinets/boxes shall be closed.	x			
1926.701 (b)	Reinforcing steel onto which employees could fall shall be guarded.			x	
1926.1053 (b) (1)	Portable ladder side rails extend at least 3 feet or be secured at top.			x	
1926.651 (j) (2)	Excavations shall have materials or equipment placed at least 2 feet from the edge.			x	
1926.651 (c) (2)	Excavations shall have a safe means of egress such as ladders, ramps, etc.	x			
1926.150 (c) (1)	Portable fire fighting equipment shall be provided and extinguishers shall be inspected periodically.			x	
1926.102 (a) (1)	Eye and face protection shall be provided.	x			
1926.300 (b) (2)	Guards for power tools shall be used and moving parts of equipment shall be guarded.	x			
1926.350 (a) (9)	Oxygen cylinders in storage shall be separated from fuel gas cylinders by at least 20 feet or a ½ fire resistance barrier.			x	

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.405 (a) (2) (ii) (e) & (f)	Temporary lights shall be protected from breakage, not suspended by their cords and extension cord.			X	
1926.405 (a) (2) (ii) (j)	Extension cords used with portable electric tools shall be of three wire type and designed for hard or extra hard usage.	x			
1926.105 (a)	Workplaces more than 25 feet above the ground or water shall have safety nets when ladder, safety line/belts, temporary floors, scaffolds, catch platform are not practical.			x	
1926.1051 (a)	Stairway or ladder shall be provided at all access points where there is a break in elevation of 19 inches or more.			x	
1926.451 (a) (2)	Scaffolding footing or anchorage shall be sound, rigid and capable of carrying the maximum intended load.			x	
1926.500 (c) (1) (old standard)	Wall opening shall be guarded.			x	
1926.404 (f) (7)	Electrical equipment connected by cord and plug shall be grounded except if there is an isolating transformer or the tool is double insulated.	x			
1926.556 (b) (2)	When working from an aerial lift, a full body harness and lanyard attached to the boom or basket.			x	
1926.501 (b) (1) (new standard)	Guardrails, safety nets or personal fall arrest system shall be used at 6 feet or more.			x	

		In Compliance	Out of Compliance	N/A	
Standard	Title	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Corrective Action Taken and Date
1926.451 (a) (14)	Scaffold planking shall extend over their end support not less than 6 inches and not more than 12 inches.			x	
1926.602 (a) (9)	Bi-directional earth moving equipment shall have audible alarms.	x			
1926.451 (a) (3)	Scaffolding shall be erected, moved, dismantled or altered under the supervision of a competent person.			x	
1926.550 (b) (2)	Cranes, crawler, truck or locomotive, shall meet the design, testing, maintenance, and operation per ANSI B30.5_1968. The most recent certification shall be on file until a new one is prepared.			x	

Comments:

Newman continued excavation and earth work in S. E. zone. Continued to fill and compact.

CVE fabricators tied rebar on stem forms.

4 pumps at compass points monitored air throughout the day.



## 3<sup>RD</sup> WEST SUBSTATION REMEDIATION PROJECT

# HEALTH SAFETY MANAGER (HSM)

### DAILY CHECKLIST

DATE: 10/31/11

#### General

- ☒ Work area Health and Safety Inspection
- NA Review and if necessary update Activity Hazard Analyses (AHA) based on planned site activities for the day
- NA Safety Planning or "Tailgate" mandatory meeting for all employees and contractors prior to commencement of any site work. Instruction, review hazards, health & safety issues and any modifications to the CSHASP
- NA Site hazard and safety instruction for all first time employees, contractors or visitors
- NA Complete Employee Meeting Record Form B (where applicable)
- NA Document required Respirator Training completion with Form H
- NA Record times and numbers of dump trucks and trailers as they leave the site with contaminated material.
- NA Confirm return of waste material manifest documents for each load with site manager.
- NA Complete all CSHASP Forms (for applicable activities planned for that day)
  - NA Illness/Injury Report Form A
  - NA Site-Specific Training Record Form C
  - NA Hot Work Permit Form D
  - NA Trench/Evacuation Permit Form E
  - NA Combined Space Entry Permit Form F
  - NA Exclusion zone operations are practiced as instructed.
  - NA Decontamination unit is working properly.
  - NA Workers are using decontamination unit as instructed.
  - NA Workers use personal protective equipment properly.
- ☒ Set air samples at cardinal compass points around exclusion zone. Check throughout the day to ensure proper operation.
- ☒ Observe control measures for dust and fugitive materials i.e. watering excavation sites and track out prevention.
- ☒ Review sign-in/sign-out log throughout and at the end of the workday.
- ☒ Secure the site at the end of the workday

#### Sampling

- NA Soil Confirmation sampling for any newly excavated areas
- ☒ Stationary Air Monitoring during contaminated soil removal around the perimeter of the exclusions zone
- NA Personal Breathing Zone Monitoring on personnel conducting contaminated dust and soil removal
- NA Digitally photograph each sample location and at any place field sampling personnel determined necessary

- NA      Electronically file photo files into the on-site database
- ☒      Complete Field Documentation
  - ☒      Field Sample Data Sheets (FSDS)
  - ☒      Logbook
- NA      On-site computer database
- ☒      Label each sample media with a unique number
- ☒      Seal sample(s) in zip lock plastic bags
- ☒      Complete and include Chain of Custody (COC) Form required for shipping of samples to appropriate laboratory
- ☒      Package samples for transport IAW SOP 2-1, Packaging and Shipping of Environmental Samples
- NA      Review and disseminate sample results as received from the laboratories to Project Manager and other appropriate managers and employees
- NA      Electronically file sample reports into on-site database



## 3<sup>rd</sup> West Substation Site Project Safety Audit

Project: 3<sup>rd</sup> West Sub Station

Date: 11/01/11

Location: 3<sup>rd</sup> West, 1<sup>st</sup> South, SLC

Job Number: \_\_\_\_\_

Survey Conducted By: Justin Kargis

Title: \_\_\_\_\_

		In Compliance	Out of Compliance	N/A	
Standard	Title	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Corrective Action Taken and Date
1926.59	Hazard Communication Program, List of Chemicals, Training, MSDSs.			x	
1926.500 (b) & (d) (old standard)	Guardrails on open sided floors, floor holes and runways.			x	
1926.404 (b)	Ground fault circuit interrupters or an assured equipment grounding conductor program in use.			x	
1926.451 (b)	The employer shall instruct each employee in the recognition and avoidance of unsafe conditions.			x	
1926.451 (d)	Tubular welded scaffolds shall be properly braced so that they are plumb, square and rigid; legs on plumb, adjustable, mud sills, etc. to support the maximum load; guardrails and toeboards shall be installed.			x	
1926.100 (a)	Head protection, where there is a possible danger of head injury.	x			

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.652 (a) (1)	Excavation protective systems; examination by competent person when less than 5 feet in depth.			x	
1926.20 (b) (2)	Employer responsibility to initiate and maintain safety and health programs.	x			
1926.20 (b) (1)	Employer responsibility to provide for frequent and regular inspections by designated competent persons.			x	
1926.451 (e)	Manually propelled scaffolds shall have tight planking for the full width, platforms secured, ladder or stairway provided, suitable footing, stand plumbs, wheels locked, guardrails and toeboards.			x	
1926.1052 (c) (1)	Stair rail and handrail along each unprotected edge.			x	
1926.25 (a)	Debris, scrap lumber with protruding nails, not cleared for work areas, stairs and around structures.			x	
1926.50	First aid shall be available in the absence of an infirmary, or other that is reasonably accessible; first aid supplies shall be accessible and telephone numbers posted.			x	
1926.451 (a) (13)	Scaffolding safe access not provided by ladder or equivalent.			x	
1926.651 (k) (1)	Excavations, protective systems, inspected daily by a competent person and as needed.			x	
1926.403 (b) (2)	Employer shall ensure electrical equipment is free from recognized hazards, is suitable, used in accordance with the listing, labeling or certification.			x	

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (4)	Scaffolding shall have guardrails and toeboards when more than 10 feet high and when less than 45 inches of work space.			x	
1926.405 (g) (2)	Flexible cords shall be used without splice or tap; strain relief shall be provided.			x	
1926.405 (b)	Electrical boxes, fittings shall have covers, faceplates or canopy and holes shall be smooth where cords pass through; and unused openings in cabinets/boxes shall be closed.	x			
1926.701 (b)	Reinforcing steel onto which employees could fall shall be guarded.			x	
1926.1053 (b) (1)	Portable ladder side rails extend at least 3 feet or be secured at top.			x	
1926.651 (j) (2)	Excavations shall have materials or equipment placed at least 2 feet from the edge.			x	
1926.651 (c) (2)	Excavations shall have a safe means of egress such as ladders, ramps, etc.			x	
1926.150 (c) (1)	Portable fire fighting equipment shall be provided and extinguishers shall be inspected periodically.			x	
1926.102 (a) (1)	Eye and face protection shall be provided.	x			
1926.300 (b) (2)	Guards for power tools shall be used and moving parts of equipment shall be guarded.			x	
1926.350 (a) (9)	Oxygen cylinders in storage shall be separated from fuel gas cylinders by at least 20 feet or a 1/2 fire resistance barrier.			x	

		In Compliance	Out of Compliance	N/A	Corrective Action Taken and
Standard	Title	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Date
1926.405 (a) (2) (ii) (e) & (f)	Temporary lights shall be protected from breakage, not suspended by their cords and extension cord.			X	
1926.405 (a) (2) (ii) (j)	Extension cords used with portable electric tools shall be of three wire type and designed for hard or extra hard usage.			x	
1926.105 (a)	Workplaces more than 25 feet above the ground or water shall have safety nets when ladder, safety line/belts, temporary floors, scaffolds, catch platform are not practical.			x	
1926.1051 (a)	Stairway or ladder shall be provided at all access points where there is a break in elevation of 19 inches or more.			x	
1926.451 (a) (2)	Scaffolding footing or anchorage shall be sound, rigid and capable of carrying the maximum intended load.			x	
1926.500 (c) (1) (old standard)	Wall opening shall be guarded.			x	
1926.404 (f) (7)	Electrical equipment connected by cord and plug shall be grounded except if there is an isolating transformer of the tool is double insulated.			x	
1926.556 (b) (2)	When working from an aerial lift, a full body harness and lanyard attached to the boom or basket.			x	
1926.501 (b) (1) (new standard)	Guardrails, safety nets or personal fall arrest system shall be used at 6 feet or more.			x	

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (14)	Scaffold planking shall extend over their end support not less than 6 inches and not more than 12 inches.	<input type="checkbox"/>	<input type="checkbox"/>	x	
1926.602 (a) (9)	Bi-directional earth moving equipment shall have audible alarms.	x	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (3)	Scaffolding shall be erected, moved, dismantled or altered under the supervision of a competent person.	<input type="checkbox"/>	<input type="checkbox"/>	x	
1926.550 (b) (2)	Cranes, crawler, truck or locomotive, shall meet the design, testing, maintenance, and operation per ANSI B30.5_1968. The most recent certification shall be on file until a new one is prepared.	<input type="checkbox"/>	<input type="checkbox"/>	x	

Comments:

Inclement weather with strong winds and substantial precipitation throughout the day hindered created unfavorable work conditions.

CVE arrived on site and waited until about 8:45 for weather to pass.

All personnel had departed and site was secured by 10 am.



## 3<sup>rd</sup> West Substation Site Project Safety Audit

Project: 3<sup>rd</sup> West Sub Station

Date: 11/02/11

Location: 3<sup>rd</sup> West, 1<sup>st</sup> South, SLC

Job Number: \_\_\_\_\_

Survey Conducted By: Justin Kargis

Title: \_\_\_\_\_

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.59	Hazard Communication Program, List of Chemicals, Training, MSDSs.			x	
1926.500 (b) & (d) (old standard)	Guardrails on open sided floors, floor holes and runways.			x	
1926.404 (b)	Ground fault circuit interrupters or an assured equipment grounding conductor program in use.	x			
1926.451 (b)	The employer shall instruct each employee in the recognition and avoidance of unsafe conditions.			x	
1926.451 (d)	Tubular welded scaffolds shall be properly braced so that they are plumb, square and rigid; legs on plumb, adjustable, mud sills, etc. to support the maximum load; guardrails and toe boards shall be installed.			x	
1926.100 (a)	Head protection, where there is a possible danger of head injury.	x			



<b>Standard</b>	<b>Title</b>	<b>In Compliance</b>	<b>Out of Compliance</b>	<b>N/A</b>	<b>Corrective Action Taken and Date</b>
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.652 (a) (1)	Excavation protective systems; examination by competent person when less than 5 feet in depth.			x	
1926.20 (b) (2)	Employer responsibility to initiate and maintain safety and health programs.	x			
1926.20 (b) (1)	Employer responsibility to provide for frequent and regular inspections by designated competent persons.			x	
1926.451 (e)	Manually propelled scaffolds shall have tight planking for the full width, platforms secured, ladder or stairway provided, suitable footing, stand plumbs, wheels locked, guardrails and toe boards.			x	
1926.1052 (c) (1)	Stair rail and handrail along each unprotected edge.			x	
1926.25 (a)	Debris, scrap lumber with protruding nails, not cleared for work areas, stairs and around structures.			x	
1926.50	First aid shall be available in the absence of an infirmary, or other that is reasonably accessible; first aid supplies shall be accessible and telephone numbers posted.			x	
1926.451 (a) (13)	Scaffolding safe access not provided by ladder or equivalent.			x	
1926.651 (k) (1)	Excavations, protective systems, inspected daily by a competent person and as needed.			x	
1926.403 (b) (2)	Employer shall ensure electrical equipment is free from recognized hazards, is suitable, used in accordance with the listing, labeling or certification.	x			

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.451 (a) (4)	Scaffolding shall have guardrails and toe boards when more than 10 feet high and when less than 45 inches of work space.			x	
1926.405 (g) (2)	Flexible cords shall be used without splice or tap; strain relief shall be provided.			x	
1926.405 (b)	Electrical boxes, fittings shall have covers, faceplates or canopy and holes shall be smooth where cords pass through; and unused openings in cabinets/boxes shall be closed.	x			
1926.701 (b)	Reinforcing steel onto which employees could fall shall be guarded.			x	
1926.1053 (b) (1)	Portable ladder side rails extend at least 3 feet or be secured at top.			x	
1926.651 (j) (2)	Excavations shall have materials or equipment placed at least 2 feet from the edge.			x	
1926.651 (c) (2)	Excavations shall have a safe means of egress such as ladders, ramps, etc.	x			
1926.150 (c) (1)	Portable fire fighting equipment shall be provided and extinguishers shall be inspected periodically.			x	
1926.102 (a) (1)	Eye and face protection shall be provided.	x			
1926.300 (b) (2)	Guards for power tools shall be used and moving parts of equipment shall be guarded.	x			
1926.350 (a) (9)	Oxygen cylinders in storage shall be separated from fuel gas cylinders by at least 20 feet or a ½ fire resistance barrier.			x	

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.405 (a) (2) (ii) (e) & (f)	Temporary lights shall be protected from breakage, not suspended by their cords and extension cord.			X	
1926.405 (a) (2) (ii) (j)	Extension cords used with portable electric tools shall be of three wire type and designed for hard or extra hard usage.	x			
1926.105 (a)	Workplaces more than 25 feet above the ground or water shall have safety nets when ladder, safety line/belts, temporary floors, scaffolds, catch platform are not practical.			x	
1926.1051 (a)	Stairway or ladder shall be provided at all access points where there is a break in elevation of 19 inches or more.			x	
1926.451 (a) (2)	Scaffolding footing or anchorage shall be sound, rigid and capable of carrying the maximum intended load.			x	
1926.500 (c) (1) (old standard)	Wall opening shall be guarded.			x	
1926.404 (f) (7)	Electrical equipment connected by cord and plug shall be grounded except if there is an isolating transformer or the tool is double insulated.	x			
1926.556 (b) (2)	When working from an aerial lift, a full body harness and lanyard attached to the boom or basket.			x	
1926.501 (b) (1) (new standard)	Guardrails, safety nets or personal fall arrest system shall be used at 6 feet or more.			x	

		In Compliance	Out of Compliance	N/A	
Standard	Title	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Corrective Action Taken and Date
1926.451 (a) (14)	Scaffold planking shall extend over their end support not less than 6 inches and not more than 12 inches.	<input type="checkbox"/>	<input type="checkbox"/>	x	
1926.602 (a) (9)	Bi-directional earth moving equipment shall have audible alarms.	x	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (3)	Scaffolding shall be erected, moved, dismantled or altered under the supervision of a competent person.	<input type="checkbox"/>	<input type="checkbox"/>	x	
1926.550 (b) (2)	Cranes, crawler, truck or locomotive, shall meet the design, testing, maintenance, and operation per ANSI B30.5_1968. The most recent certification shall be on file until a new one is prepared.	<input type="checkbox"/>	<input type="checkbox"/>	x	

Comments:

Newman continued excavation and earth work in S. E. zone. Continued to fill and compact.

CVE fabricators worked on and set some pier form on spread footings.

Scott Collard, Mike Shepherd on site in the morning to discuss upcoming schedule over the next few months.

4 pumps at compass points monitored air throughout the day.

# 3<sup>RD</sup> WEST SUBSTATION REMEDIATION PROJECT

## HEALTH SAFETY MANAGER (HSM)

### DAILY CHECKLIST

DATE: 11/02/11

#### General

- ☒ Work area Health and Safety Inspection
- NA Review and if necessary update Activity Hazard Analyses (AHA) based on planned site activities for the day
- NA Safety Planning or "Tailgate" mandatory meeting for all employees and contractors prior to commencement of any site work. Instruction, review hazards, health & safety issues and any modifications to the CSHASP
- NA Site hazard and safety instruction for all first time employees, contractors or visitors
- NA Complete Employee Meeting Record Form B (where applicable)
- NA Document required Respirator Training completion with Form H
- NA Record times and numbers of dump trucks and trailers as they leave the site with contaminated material.
- NA Confirm return of waste material manifest documents for each load with site manager.
- NA Complete all CSHASP Forms (for applicable activities planned for that day)
  - NA Illness/Injury Report Form A
  - NA Site-Specific Training Record Form C
  - NA Hot Work Permit Form D
  - NA Trench/Evacuation Permit Form E
  - NA Combined Space Entry Permit Form F
  - NA Exclusion zone operations are practiced as instructed.
    - NA Decontamination unit is working properly.
    - NA Workers are using decontamination unit as instructed.
    - NA Workers use personal protective equipment properly.
- ☒ Set air samples at cardinal compass points around exclusion zone. Check throughout the day to ensure proper operation.
- ☒ Observe control measures for dust and fugitive materials i.e. watering excavation sites and track out prevention.
- ☒ Review sign-in/sign-out log throughout and at the end of the workday.
- ☒ Secure the site at the end of the workday

#### Sampling

- NA Soil Confirmation sampling for any newly excavated areas
- ☒ Stationary Air Monitoring during contaminated soil removal around the perimeter of the exclusions zone
- NA Personal Breathing Zone Monitoring on personnel conducting contaminated dust and soil removal
- NA Digitally photograph each sample location and at any place field sampling personnel determined necessary

- NA      Electronically file photo files into the on-site database
- ☒      Complete Field Documentation
  - ☒      Field Sample Data Sheets (FSDS)
  - ☒      Logbook
- NA      On-site computer database
- ☒      Label each sample media with a unique number
- ☒      Seal sample(s) in zip lock plastic bags
- ☒      Complete and include Chain of Custody (COC) Form required for shipping of samples to appropriate laboratory
- ☒      Package samples for transport IAW SOP 2-1, Packaging and Shipping of Environmental Samples
- NA      Review and disseminate sample results as received from the laboratories to Project Manager and other appropriate managers and employees
- NA      Electronically file sample reports into on-site database



## 3<sup>rd</sup> West Substation Site Project Safety Audit

Project: 3<sup>rd</sup> West Sub Station

Date: 11/03/11

Location: 3<sup>rd</sup> West, 1<sup>st</sup> South, SLC

Job Number: \_\_\_\_\_

Survey Conducted By: Justin Kargis

Title: \_\_\_\_\_

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.59	Hazard Communication Program, List of Chemicals, Training, MSDSs.			x	
1926.500 (b) & (d) (old standard)	Guardrails on open sided floors, floor holes and runways.			x	
1926.404 (b)	Ground fault circuit interrupters or an assured equipment grounding conductor program in use.	x			
1926.451 (b)	The employer shall instruct each employee in the recognition and avoidance of unsafe conditions.			x	
1926.451 (d)	Tubular welded scaffolds shall be properly braced so that they are plumb, square and rigid; legs on plumb, adjustable, mud sills, etc. to support the maximum load; guardrails and toe boards shall be installed.			x	
1926.100 (a)	Head protection, where there is a possible danger of head injury.	x			

<i>Standard</i>	<i>Title</i>	In Compliance	Out of Compliance	N/A	<i>Corrective Action Taken and Date</i>
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.652 (a) (1)	Excavation protective systems; examination by competent person when less than 5 feet in depth.			x	
1926.20 (b) (2)	Employer responsibility to initiate and maintain safety and health programs.	x			
1926.20 (b) (1)	Employer responsibility to provide for frequent and regular inspections by designated competent persons.			x	
1926.451 (e)	Manually propelled scaffolds shall have tight planking for the full width, platforms secured, ladder or stairway provided, suitable footing, stand plumbs, wheels locked, guardrails and toe boards.			x	
1926.1052 (c) (1)	Stair rail and handrail along each unprotected edge.			x	
1926.25 (a)	Debris, scrap lumber with protruding nails, not cleared for work areas, stairs and around structures.			x	
1926.50	First aid shall be available in the absence of an infirmary, or other that is reasonably accessible; first aid supplies shall be accessible and telephone numbers posted.			x	
1926.451 (a) (13)	Scaffolding safe access not provided by ladder or equivalent.			x	
1926.651 (k) (1)	Excavations, protective systems, inspected daily by a competent person and as needed.			x	
1926.403 (b) (2)	Employer shall ensure electrical equipment is free from recognized hazards, is suitable, used in accordance with the listing, labeling or certification.	x			



Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (4)	Scaffolding shall have guardrails and toe boards when more than 10 feet high and when less than 45 inches of work space.			x	
1926.405 (g) (2)	Flexible cords shall be used without splice or tap; strain relief shall be provided.			x	
1926.405 (b)	Electrical boxes, fittings shall have covers, faceplates or canopy and holes shall be smooth where cords pass through; and unused openings in cabinets/boxes shall be closed.	x			
1926.701 (b)	Reinforcing steel onto which employees could fall shall be guarded.			x	
1926.1053 (b) (1)	Portable ladder side rails extend at least 3 feet or be secured at top.			x	
1926.651 (j) (2)	Excavations shall have materials or equipment placed at least 2 feet from the edge.			x	
1926.651 (c) (2)	Excavations shall have a safe means of egress such as ladders, ramps, etc.	x			
1926.150 (c) (1)	Portable fire fighting equipment shall be provided and extinguishers shall be inspected periodically.			x	
1926.102 (a) (1)	Eye and face protection shall be provided.	x			
1926.300 (b) (2)	Guards for power tools shall be used and moving parts of equipment shall be guarded.	x			
1926.350 (a) (9)	Oxygen cylinders in storage shall be separated from fuel gas cylinders by at least 20 feet or a ½ fire resistance barrier.			x	

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.405 (a) (2) (ii) (e) & (f)	Temporary lights shall be protected from breakage, not suspended by their cords and extension cord.			X	
1926.405 (a) (2) (ii) (j)	Extension cords used with portable electric tools shall be of three wire type and designed for hard or extra hard usage.	x			
1926.105 (a)	Workplaces more than 25 feet above the ground or water shall have safety nets when ladder, safety line/belts, temporary floors, scaffolds, catch platform are not practical.			x	
1926.1051 (a)	Stairway or ladder shall be provided at all access points where there is a break in elevation of 19 inches or more.			x	
1926.451 (a) (2)	Scaffolding footing or anchorage shall be sound, rigid and capable of carrying the maximum intended load.			x	
1926.500 (c) (1) (old standard)	Wall opening shall be guarded.			x	
1926.404 (f) (7)	Electrical equipment connected by cord and plug shall be grounded except if there is an isolating transformer or the tool is double insulated.	x			
1926.556 (b) (2)	When working from an aerial lift, a full body harness and lanyard attached to the boom or basket.			x	
1926.501 (b) (1) (new standard)	Guardrails, safety nets or personal fall arrest system shall be used at 6 feet or more.			x	

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (14)	Scaffold planking shall extend over their end support not less than 6 inches and not more than 12 inches.			x	
1926.602 (a) (9)	Bi-directional earth moving equipment shall have audible alarms.	x			
1926.451 (a) (3)	Scaffolding shall be erected, moved, dismantled or altered under the supervision of a competent person.			x	
1926.550 (b) (2)	Cranes, crawler, truck or locomotive, shall meet the design, testing, maintenance, and operation per ANSI B30.5_1968. The most recent certification shall be on file until a new one is prepared.			x	

**Comments:**

Newman continued excavation and earth work in S. E. zone. Continued to fill and compact.

CVE fabricators worked on and set pier form on spread footings.

4 pumps at compass points monitored air throughout the day, north sample cassette dislodged from tubing and was lost. Only South, East, and West samples submitted for today.

# 3<sup>RD</sup> WEST SUBSTATION REMEDIATION PROJECT

## HEALTH SAFETY MANAGER (HSM)

### DAILY CHECKLIST

DATE: 11/03/11

#### General

- ☒ Work area Health and Safety Inspection
- NA Review and if necessary update Activity Hazard Analyses (AHA) based on planned site activities for the day
- NA Safety Planning or "Tailgate" mandatory meeting for all employees and contractors prior to commencement of any site work. Instruction, review hazards, health & safety issues and any modifications to the CSHASP
- NA Site hazard and safety instruction for all first time employees, contractors or visitors
- NA Complete Employee Meeting Record Form B (where applicable)
- NA Document required Respirator Training completion with Form H
- NA Record times and numbers of dump trucks and trailers as they leave the site with contaminated material.
- NA Confirm return of waste material manifest documents for each load with site manager.
- NA Complete all CSHASP Forms (for applicable activities planned for that day)
  - NA Illness/Injury Report Form A
  - NA Site-Specific Training Record Form C
  - NA Hot Work Permit Form D
  - NA Trench/Evacuation Permit Form E
  - NA Combined Space Entry Permit Form F
  - NA Exclusion zone operations are practiced as instructed.
  - NA Decontamination unit is working properly.
  - NA Workers are using decontamination unit as instructed.
  - NA Workers use personal protective equipment properly.
- ☒ Set air samples at cardinal compass points around exclusion zone. Check throughout the day to ensure proper operation.
- ☒ Observe control measures for dust and fugitive materials i.e. watering excavation sites and track out prevention.
- ☒ Review sign-in/sign-out log throughout and at the end of the workday.
- ☒ Secure the site at the end of the workday

#### Sampling

- NA Soil Confirmation sampling for any newly excavated areas
- ☒ Stationary Air Monitoring during contaminated soil removal around the perimeter of the exclusions zone
- NA Personal Breathing Zone Monitoring on personnel conducting contaminated dust and soil removal
- NA Digitally photograph each sample location and at any place field sampling personnel determined necessary

- NA      Electronically file photo files into the on-site database
- ☒      Complete Field Documentation
  - ☒      Field Sample Data Sheets (FSDS)
  - ☒      Logbook
- NA      On-site computer database
- ☒      Label each sample media with a unique number
- ☒      Seal sample(s) in zip lock plastic bags
- ☒      Complete and include Chain of Custody (COC) Form required for shipping of samples to appropriate laboratory
- ☒      Package samples for transport IAW SOP 2-1, Packaging and Shipping of Environmental Samples
- NA      Review and disseminate sample results as received from the laboratories to Project Manager and other appropriate managers and employees
- NA      Electronically file sample reports into on-site database



## 3<sup>rd</sup> West Substation Site Project Safety Audit

Project: 3<sup>rd</sup> West Sub Station

Date: 11/04/11

Location: 3<sup>rd</sup> West, 1<sup>st</sup> South, SLC

Job Number: \_\_\_\_\_

Survey Conducted By: Justin Kargis

Title: \_\_\_\_\_

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.59	Hazard Communication Program, List of Chemicals, Training, MSDSs.			x	
1926.500 (b) & (d) (old standard)	Guardrails on open sided floors, floor holes and runways.			x	
1926.404 (b)	Ground fault circuit interrupters or an assured equipment grounding conductor program in use.	x			
1926.451 (b)	The employer shall instruct each employee in the recognition and avoidance of unsafe conditions.			x	
1926.451 (d)	Tubular welded scaffolds shall be properly braced so that they are plumb, square and rigid; legs on plumb, adjustable, mud sills, etc. to support the maximum load; guardrails and toe boards shall be installed.			x	
1926.100 (a)	Head protection, where there is a possible danger of head injury.	x			

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.652 (a) (1)	Excavation protective systems; examination by competent person when less than 5 feet in depth.			x	
1926.20 (b) (2)	Employer responsibility to initiate and maintain safety and health programs.	x			
1926.20 (b) (1)	Employer responsibility to provide for frequent and regular inspections by designated competent persons.			x	
1926.451 (e)	Manually propelled scaffolds shall have tight planking for the full width, platforms secured, ladder or stairway provided, suitable footing, stand plumbs, wheels locked, guardrails and toe boards.			x	
1926.1052 (c) (1)	Stair rail and handrail along each unprotected edge.			x	
1926.25 (a)	Debris, scrap lumber with protruding nails, not cleared for work areas, stairs and around structures.			x	
1926.50	First aid shall be available in the absence of an infirmary, or other that is reasonably accessible; first aid supplies shall be accessible and telephone numbers posted.			x	
1926.451 (a) (13)	Scaffolding safe access not provided by ladder or equivalent.			x	
1926.651 (k) (1)	Excavations, protective systems, inspected daily by a competent person and as needed.			x	
1926.403 (b) (2)	Employer shall ensure electrical equipment is free from recognized hazards, is suitable, used in accordance with the listing, labeling or certification.	x			

		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.451 (a) (4)	Scaffolding shall have guardrails and toe boards when more than 10 feet high and when less than 45 inches of work space.			x	
1926.405 (g) (2)	Flexible cords shall be used without splice or tap; strain relief shall be provided.			x	
1926.405 (b)	Electrical boxes, fittings shall have covers, faceplates or canopy and holes shall be smooth where cords pass through; and unused openings in cabinets/boxes shall be closed.	x			
1926.701 (b)	Reinforcing steel onto which employees could fall shall be guarded.			x	
1926.1053 (b) (1)	Portable ladder side rails extend at least 3 feet or be secured at top.			x	
1926.651 (j) (2)	Excavations shall have materials or equipment placed at least 2 feet from the edge.			x	
1926.651 (c) (2)	Excavations shall have a safe means of egress such as ladders, ramps, etc.	x			
1926.150 (c) (1)	Portable fire fighting equipment shall be provided and extinguishers shall be inspected periodically.			x	
1926.102 (a) (1)	Eye and face protection shall be provided.	x			
1926.300 (b) (2)	Guards for power tools shall be used and moving parts of equipment shall be guarded.	x			
1926.350 (a) (9)	Oxygen cylinders in storage shall be separated from fuel gas cylinders by at least 20 feet or a ½ fire resistance barrier.			x	



		In Compliance	Out of Compliance	N/A	
<i>Standard</i>	<i>Title</i>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Corrective Action Taken and Date</i>
1926.405 (a) (2) (ii) (e) & (f)	Temporary lights shall be protected from breakage, not suspended by their cords and extension cord.			X	
1926.405 (a) (2) (ii) (j)	Extension cords used with portable electric tools shall be of three wire type and designed for hard or extra hard usage.	x			
1926.105 (a)	Workplaces more than 25 feet above the ground or water shall have safety nets when ladder, safety line/belts, temporary floors, scaffolds, catch platform are not practical.			x	
1926.1051 (a)	Stairway or ladder shall be provided at all access points where there is a break in elevation of 19 inches or more.	x			
1926.451 (a) (2)	Scaffolding footing or anchorage shall be sound, rigid and capable of carrying the maximum intended load.			x	
1926.500 (c) (1) (old standard)	Wall opening shall be guarded.			x	
1926.404 (f) (7)	Electrical equipment connected by cord and plug shall be grounded except if there is an isolating transformer or the tool is double insulated.	x			
1926.556 (b) (2)	When working from an aerial lift, a full body harness and lanyard attached to the boom or basket.			x	
1926.501 (b) (1) (new standard)	Guardrails, safety nets or personal fall arrest system shall be used at 6 feet or more.			x	

Standard	Title	In Compliance	Out of Compliance	N/A	Corrective Action Taken and Date
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
1926.451 (a) (14)	Scaffold planking shall extend over their end support not less than 6 inches and not more than 12 inches.	x			
1926.602 (a) (9)	Bi-directional earth moving equipment shall have audible alarms.	x			
1926.451 (a) (3)	Scaffolding shall be erected, moved, dismantled or altered under the supervision of a competent person.	x			
1926.550 (b) (2)	Cranes, crawler, truck or locomotive, shall meet the design, testing, maintenance, and operation per ANSI B30.5_1968. The most recent certification shall be on file until a new one is prepared.			x	

Comments:

Newman continued excavation and earth work in S. E. zone. Found scrap pieces of geo grid material and a small amount of darker soil near east gate.

CVE fabricators pored columns for G structures in S. E. zone.

4 pumps at compass points monitored air throughout the day.

R&R sampled soil that had been brought into zone 1 for backfilling along the west side of control building. 1 sample taken to Dixon for analysis. Soil was darker and more brown than other fill material used in other areas of the site.

CVE brought in vacuum truck to dig a hole for a new power line pole outside the S.W. corner of zone 1. Water was applied continuously to control dust and hole was covered upon completion. This excavation did appear to penetrate native soil.

# 3<sup>RD</sup> WEST SUBSTATION REMEDIATION PROJECT

## HEALTH SAFETY MANAGER (HSM)

### DAILY CHECKLIST

DATE: 11/04/11


#### General

- ☒ Work area Health and Safety Inspection
- NA Review and if necessary update Activity Hazard Analyses (AHA) based on planned site activities for the day
- NA Safety Planning or "Tailgate" mandatory meeting for all employees and contractors prior to commencement of any site work. Instruction, review hazards, health & safety issues and any modifications to the CSHASP
- NA Site hazard and safety instruction for all first time employees, contractors or visitors
- NA Complete Employee Meeting Record Form B (where applicable)
- NA Document required Respirator Training completion with Form H
- NA Record times and numbers of dump trucks and trailers as they leave the site with contaminated material.
- NA Confirm return of waste material manifest documents for each load with site manager.
- NA Complete all CSHASP Forms (for applicable activities planned for that day)
  - NA Illness/Injury Report Form A
  - NA Site-Specific Training Record Form C
  - NA Hot Work Permit Form D
  - NA Trench/Evacuation Permit Form E
  - NA Combined Space Entry Permit Form F
  - NA Exclusion zone operations are practiced as instructed.
    - NA Decontamination unit is working properly.
    - NA Workers are using decontamination unit as instructed.
    - NA Workers use personal protective equipment properly.
- ☒ Set air samples at cardinal compass points around exclusion zone. Check throughout the day to ensure proper operation.
- ☒ Observe control measures for dust and fugitive materials i.e. watering excavation sites and track out prevention.
- ☒ Review sign-in/sign-out log throughout and at the end of the workday.
- ☒ Secure the site at the end of the workday

#### Sampling

- ☒ Soil Confirmation sampling for any newly excavated areas
- ☒ Stationary Air Monitoring during contaminated soil removal around the perimeter of the exclusions zone
- NA Personal Breathing Zone Monitoring on personnel conducting contaminated dust and soil removal
- NA Digitally photograph each sample location and at any place field sampling personnel determined necessary

- NA      Electronically file photo files into the on-site database
- ☒      Complete Field Documentation
  - ☒      Field Sample Data Sheets (FSDS)
  - ☒      Logbook
- NA      On-site computer database
- ☒      Label each sample media with a unique number
- ☒      Seal sample(s) in zip lock plastic bags
- ☒      Complete and include Chain of Custody (COC) Form required for shipping of samples to appropriate laboratory
- ☒      Package samples for transport IAW SOP 2-1, Packaging and Shipping of Environmental Samples
- NA      Review and disseminate sample results as received from the laboratories to Project Manager and other appropriate managers and employees
- NA      Electronically file sample reports into on-site database



**PHOTO 1**



**PHOTO 2**



**PHOTO 3**

## **R & REnvironmental, Inc.**

47 West 9000 South, Suite #2, Sandy, Utah 84070  
(801) 352-2380 • Fax: (801) 352-2381

PROJECT NO:

DESIGNED BY:

SCALE:

REVIEWED BY:  
DCR

DRAWN BY:  
JMK

DATE  
10/31/2011

FILE:

## **SITE PHOTOGRAPHS**



**3<sup>rd</sup> West Substation  
"2011 Upgrade Project"  
Salt Lake City, Utah**





**PHOTO 1**



**PHOTO 2**



**PHOTO 3**

## **R & R Environmental, Inc.**

47 West 9000 South, Suite #2, Sandy, Utah 84070  
(801) 352-2380 • Fax: (801) 352-2381

PROJECT NO:

DESIGNED BY:

SCALE:

REVIEWED BY:

DCR

DRAWN BY:

JMK

DATE

11/02/2011

FILE:

## **SITE PHOTOGRAPHS**



**3<sup>rd</sup> West Substation  
"2011 Upgrade Project"  
Salt Lake City, Utah**



PHOTO 1



PHOTO 2



PHOTO 3

## **R & REnvironmental, Inc.**

47 West 9000 South, Suite #2, Sandy, Utah 84070  
(801) 352-2380 • Fax: (801) 352-2381

PROJECT NO:

DESIGNED BY:

SCALE:

REVIEWED BY:  
DCR

DRAWN BY:

JMK

DATE

11/03/2011

FILE:

## **SITE PHOTOGRAPHS**



**3<sup>rd</sup> West Substation  
"2011 Upgrade Project"  
Salt Lake City, Utah**





PHOTO 1




PHOTO 2



PHOTO 3



PHOTO 4

## **R & R**Environmental, Inc.

47 West 9000 South, Suite #2, Sandy, Utah 84070  
(801) 352-2380 • Fax: (801) 352-2381

PROJECT NO:

DESIGNED BY:

SCALE:

REVIEWED BY:  
DCR

DRAWN BY:  
JMK

DATE:  
11-04-11

FILE:

## SITE PHOTOGRAPHS



3<sup>rd</sup> West Substation  
"2011 Upgrade Project"  
Salt Lake City, Utah






PHOTO 1




PHOTO 2



PHOTO 3



PHOTO 4

## **R & R**Environmental, Inc.

47 West 9000 South, Suite #2, Sandy, Utah 84070  
(801) 352-2380 • Fax: (801) 352-2381

PROJECT NO:

DESIGNED BY:

SCALE:

REVIEWED BY:  
DCR

DRAWN BY:  
JMK

DATE:  
11-04-11

FILE:

## SITE PHOTOGRAPHS



**3<sup>rd</sup> West Substation**  
**"2011 Upgrade Project"**  
**Salt Lake City, Utah**

# PACIFICORP OPERATIONS - Field Construction Representative Daily Log

PROJECT NAME: Third West Sub - Rebuild

DATE: Monday, October 31, 2011

PO & Work Order NO.: 3000078050 / 10035803

MAIN CONTRACTOR: Cache Valley Electric

Crew Start Time: 7:00

Crew Stop Time: 17:00

Tot Hrs mns: 10:00

FCR Start Time: 6:45

FCR Stop Time: 17:15

Tot Hrs mns: 10:30

Use military time format 00:00

WEATHER CONDITIONS: Sunny - 65 degrees

**DESCRIPTION: (work performed, general comments, instructions to contractor, # of crew members onsite.)**

R&R set up four monitors. CVE tying rebar and setting up forms for the spread footing stems (6 each). Newman continues to excavate to the north to complete the area where the final two "G" spread footings will be placed and is backfilling around the six mats that were poured last week. Newman is also excavating in the transformer foundation area. CVE will set forms and place rebar for the six spread footing stems and plan on pouring the six stems and the last two mats on Wednesday or Thursday. Tyler from PSI came by and witnessed the proof-roll of the base under the north two "G" foundations, and found it to be good. He will come back one more time for this part of the excavation when we complete the excavation of the east transformer area. Contractors: CVE = 5, Newman = 4, R&R = 1, Wilding = 1, PSI = 1.

**IF WORKING IN ENERGIZED SUBSTATION:**

Dispatcher login, name and time: Manny LuHuan 0700

Dispatcher logout, name and time: Gus Montanez 1710

**DISCREPANCIES:**

**IMMEDIATE CORRECTIVE ACTION TAKEN:**


**DELAYS OR LOST TIME ENCOUNTERED:**

**EQUIPMENT (working, delivered, idle):**

Portable toilet (2), forklift, 2 dumpsters, office trailer, conex, exclusion zone conex (2), water wagon, portable wash-down structure, trackhoe w/pavement breaker, mini-ex, bobcat, power washer, water truck, compactor, CVE tool trailer, crew truck, backhoe, dump truck.

**OSHA Recordable Safety Incidents:**

Reported by:

Time:




Russ Johnson

Field Construction Representative

# PACIFICORP OPERATIONS - Field Construction Representative Daily Log

PROJECT NAME: Third West Sub - Rebuild

DATE : Wednesday, November 2, 2011

PO & Work Order NO. : 3000078050 / 10035803

MAIN CONTRACTOR : Cache Valley Electric

Crew Start Time: 7:00

Crew Stop Time: 17:30

Tot Hrs mns: 10:30

FCR Start Time: 6:45

FCR Stop Time: 17:35

Tot Hrs mns: 10:50

Use military time format 00:00

WEATHER CONDITIONS:

Sunny, 45 degrees

DESCRIPTION: (work performed, general comments, instructions to contractor, # of crew members onsite.)

R&R set up four monitors. CVE working on setting up forms and anchor bolts for the six spread footings. Newman placing backfill around the six spread footing mats and excavating for the east transformer foundation, and hauling spoils to the storage site. Contractors: CVE = 6, Newman = 4, R&R = 1, Wilding = 1.

IF WORKING IN ENERGIZED SUBSTATION:

Dispatcher login, name and time: Barry Nielson 0655

Dispatcher logout, name and time: Gus Montanez 0535

DISCREPANCIES:

IMMEDIATE CORRECTIVE ACTION TAKEN:


DELAYS OR LOST TIME ENCOUNTERED:

Three hour down time on the bobcat while waiting for repairs to a hydraulic hose.

EQUIPMENT (working, delivered, idle):

Portable toilet (2), forklift, 2 dumpsters, office trailer, conex, exclusion zone conex (2), water wagon, portable wash-down structure, trackhoe w/pavement breaker, mini-ex, bobcat, power washer, water truck, compactor, CVE tool trailer, crew truck, backhoe, dump truck.

OSHA Recordable Safety Incidents:

Reported by:

Time:




Russ Johnson

Field Construction Representative

# PACIFICORP OPERATIONS - Field Construction Representative Daily Log

PROJECT NAME: Third West Sub - Rebuild

DATE: Thursday, November 3, 2011

PO & Work Order NO.: 3000078050 / 10035803

MAIN CONTRACTOR: Cache Valley Electric

Crew Start Time: 6:50

Crew Stop Time: 17:30

Tot Hrs mns: 10:40

FCR Start Time: 6:50

FCR Stop Time: 17:45

Tot Hrs mns: 10:55

Use military time format 00:00

WEATHER CONDITIONS: Sunny, breezy, 50 degrees

## DESCRIPTION: (work performed, general comments, instructions to contractor, # of crew members onsite.)

R&R set up four monitors. CVE working on setting up forms and anchor bolts for the six spread footings. Six spread footing stems are ready to go and CVE anticipates pouring the mats for the two north spread footing foundations on Friday, along with the six stems. Newman excavating for the east transformer foundation, backfilling around the west side of the control building foundation, and hauling spoils to the storage site. Newman also spread some gravel in the control building area as we are now needing to use the north gate for access in and out of the substation. The gravel will help in limiting any tracking outside the substation area. RMP Underground personnel (Rooster) came by today to look at the materials in the basement of the old control house and they will return in a couple of days to remove the materials they want. They have indicated that any material left in the basement after that can be scrapped. Contractors: CVE = 6, Newman = 4, R&R = 1, Wilding = 1.

## IF WORKING IN ENERGIZED SUBSTATION:

Dispatcher login, name and time:	Barry Nielson 0655
Dispatcher logout, name and time:	Gus Montanez 1745

## DISCREPANCIES:

## IMMEDIATE CORRECTIVE ACTION TAKEN:


## DELAYS OR LOST TIME ENCOUNTERED:

--

## EQUIPMENT (working, delivered, idle):

Portable toilet (2), forklift, 2 dumpsters, office trailer, conex, exclusion zone conex (2), water wagon, portable wash-down structure, trackhoe w/pavement breaker, mini-ex, bobcat, power washer, water truck, compactor, CVE tool trailer, crew truck, backhoe, dump truck.

## OSHA Recordable Safety Incidents:

Reported by:

Time:




Russ Johnson

Field Construction Representative

# PACIFICORP OPERATIONS - Field Construction Representative Daily Log

PROJECT NAME: Third West Sub - Rebuild

DATE : Friday, November 4, 2011

PO & Work Order NO. : 3000078050 / 10035803

MAIN CONTRACTOR : Cache Valley Electric

Crew Start Time: 6:50

Crew Stop Time: 17:30

Tot Hrs mns: 10:40

FCR Start Time: 6:50

FCR Stop Time: 17:35

Tot Hrs mns: 10:45

Use military time format 00:00

WEATHER CONDITIONS: Clear and Sunny in the AM, Cloudy and Breezy in the PM, 40 degrees

**DESCRIPTION: (work performed, general comments, instructions to contractor, # of crew members onsite.)**

R&R set up four monitors. CVE completed the preparation for pouring the six spread footing stems last night. They are working on the two north spread footing mats this morning in hopes of having them ready to pour at 1:00 with the stems. Started pour around 1:15 and completed the pour around 3:00. Newman excavating for the east transformer foundation, backfilling around the west side of the control building foundation, and hauling spoils to the storage site. Set one cable trench running south from the pullbox so we wouldn't have to snake the trench in between the building and the fence after the building is set. Received phone call from the trucking company that is hauling the Trachte building. They will be on site Saturday evening and will be ready for building set on Monday morning. CVE Vac-truck came on site at 2:00 and vac'd the hole for the new pole adjacent to the 6" riser near the corner of the printing building. R&R witnessed the process and felt that keeping water on the hole would alleviate any issues with hazardous materials. Contractors: Tyler, from PSI, came by around 2:45 to witness the proof roll of the excavation for the east transformer pad. He gave the proofing a thumbs up and will be back on Saturday or Monday to give a final approval when the excavation is 100%. CVE = 7, Newman = 4, R&R = 1, Wilding = 1, PSI = 1.

**IF WORKING IN ENERGIZED SUBSTATION:**

Dispatcher login, name and time:	Kim Batt 0735
Dispatcher logout, name and time:	

**DISCREPANCIES:**

**IMMEDIATE CORRECTIVE ACTION TAKEN:**

CVE indicates that they were given permission to add super to the concrete mix for todays pour and that an 8" slump was acceptable. Wilding had not been informed of this change, nor had I. The onsite specs for this job indicate that the slump is to be 2-4 inch, with 6" being acceptable if the mud is to be pumped	
No thermal protection, other than a piece of visqueen over the open top of the forms was placed on the six stems poured today. Blankets were placed on the two mats. Lows for Saturday and Sunday are expected to be 30 and 29 degrees respectively.	Advised CVE of the requirement for thermal protection for the first 48 hrs when mean temps are expected to be below 40

**DELAYS OR LOST TIME ENCOUNTERED:**

The concrete company shorted the delivery by one yard so it was necessary to order a cleanup of one yard. The mud was delivered well within the parameters for time allowed (30 mins.) between trucks, at 23 min.

**EQUIPMENT (working, delivered, idle):**

Portable toilet (2), forklift, 2 dumpsters, office trailer, conex, exclusion zone conex (2), water wagon, portable wash-down structure, trackhoe w/pavement breaker, mini-ex, bobcat, power washer, water truck, compactor, CVE tool trailer, crew truck, backhoe, dump truck, Vac-truck.

**OSHA Recordable Safety Incidents:**

Reported by:

Time:




Russ Johnson

Field Construction Representative

**REILAB** ***Reservoirs Environmental, Inc.***

November 3, 2011

Laboratory Code: RES  
Subcontract Number: NA  
Laboratory Report: RES 223514-1  
Project # / P.O. #: None Given  
Project Description: 3rd West Sub Station - RMP

Eldon Romney  
R & R Environmental  
47 West 9000 South #2  
Sandy UT 84070


Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

RES 223514-1 is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,



Jeanne Spencer Orr  
President

P: 303-964-1986  
F: 303-477-4275

5801 Logan Street, Suite 100 Denver, CO 80216

1-866-RESI-ENV  
www.reilab.com

# RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0; TDH: #30-0015

**TABLE I. TEM AIR FILTER SAMPLE DATA AND ANALYTICAL RESULTS**

**RES Job Number:** RES 223514-1  
**Client:** R & R Environmental  
**Client Project Number / P.O.:** None Given  
**Client Project Description:** 3rd West Sub Station - RMP  
**Date Samples Received:** November 2, 2011  
**Analysis Type:** TEM, AHERA  
**Turnaround:** 24 Hour  
**Date Samples Analyzed:** November 3, 2011

Client ID Number	Lab ID Number	Area Analyzed	Air Volume Sampled	Number of Asbestos Structures Detected	Analytical Sensitivity	Asbestos Concentration	Filter Loading
		(mm <sup>2</sup> )	(L)		(s/cc)	(s/cc)	(s/mm <sup>2</sup> )
3W-103111-E	EM 817882	0.0880	917	ND	0.0048	BAS	BAS
3W-103111-S	EM 817883	0.0880	916	ND	0.0048	BAS	BAS
3W-103111-N	EM 817884	0.0880	914	ND	0.0048	BAS	BAS
3W-103111-W	EM 817885	0.0880	912	ND	0.0048	BAS	BAS

NA = Not Analyzed

ND = None Detected


BAS = Below Analytical Sensitivity

Average Grid Opening in mm<sup>2</sup> = 0.011

Filter Material = Mixed Cellulose Ester

Filter Diameter = 25 mm

Effective Filter Area = 385 sq mm

  
 Digitally  
 signed by  
 Gina Vettrano  
 Date:  
 2011.11.03  
 10:45:23  
 -0800

**DATA QA**



Due Date: 11-3-11  
 Due Time: 9am

# RES LAB Reservoirs Environmental, Inc.

5801 Logan St. Denver, CO 80216 • Ph: 303 964-1986 • Fax 303-477-4275 • Toll Free: 866 RES-ENV

Pager: 303-809-2088

Page 1 of 1

## INVOICE TO: (IF DIFFERENT)

## CONTACT INFORMATION:

Company: <u>REI Environmental</u>	Company:	Contact: <u>Dave Roskelley</u>	Contact:
Address: <u>47 W. 9000 S.</u>	Address:	Phone:	Phone:
<u>Sandy, UT. 84070</u>		Fax:	Fax:
		Cell/pager: <u>801 541-1035</u>	Cell/pager:
Project Number and/or P.O. #:		Final Data Deliverable Email Address:	
Project Description/Location: <u>3rd West Sub Station - RMP</u>		<u>dave@renviro.com</u>	

ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm		REQUESTED ANALYSIS												VALID MATRIX CODES		LAB NOTES:								
PLM / PCM / TEM <u>   </u> RUSH (Same Day) <u>✓</u> PRIORITY (Next Day) <u>   </u> STANDARD (Rush PCM = 2hr, TEM = 6hr.)		PLM - Short report, Long report, Point Count	TEM - AHERA, Level II, 7402, ISO, +/-, Quant, Semi-quant, Micro-vac, ISO-Indirect Preps	PCM - 7400A, 7400B, OSHA	DUST - Total, Respirable	METALS - Analyte(s)	RCRA 8, TCLP, Welding Fume, Metals Scan	ORGANICS - METH	Salmonella: +/-	E.coli O157:H7: +/-	Listeria: +/-	Aerobic Plate Count: +/- or Quantification	E.coli: +/- or Quantification	Coliforms: +/- or Quantification	S.aureus: +/- or Quantification	Y & M: +/- or Quantification	Mold: +/- or Identification, Quantification	SAMPLER'S INITIALS OR OTHER NOTES	Air = A Bulk = B Dust = D Paint = P Soil = S Wipe = W Swab = SW F = Food Drinking Water = DW Waste Water = WW O = Other **ASTM E1792 approved wipe media only**					
CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm																			Sample Volume (L) / Area	Matrix Code	# Containers	Date Collected mm/dd/yy	Time Collected hh/mm a/p	EM Number (Laborat Use Only)
Metal(s) / Dust <u>   </u> RUSH <u>   </u> 24 hr. <u>   </u> 3-5 Day																								
RCRA 8 / Metals & Welding Fume Scan / TCLP <u>   </u> RUSH <u>   </u> 5 day <u>   </u> 10 day																								
Organics <u>   </u> 24 hr. <u>   </u> 3 day <u>   </u> 5 Day																								
MICROBIOLOGY LABORATORY HOURS: Weekdays: 9am - 6pm																								
E.coli O157:H7, Coliforms, S.aureus <u>   </u> 24 hr. <u>   </u> 2 Day <u>   </u> 3-6 Day																								
Salmonella, Listeria, E.coli, APC, Y & M <u>   </u> 48 Hr. <u>   </u> 3-5 Day																								
Mold <u>   </u> RUSH <u>   </u> 24 Hr <u>   </u> 48 Hr <u>   </u> 3 Day <u>   </u> 5 Day																								
**Turnaround times establish a laboratory priority, subject to laboratory volume and are not guaranteed. Additional fees apply for afterhours, weekends and holidays.**																								
Special Instructions:																								
Client sample ID number (Sample ID's must be unique)																								
1	3W-103111-E		X															917	A	10/31/11	817882			
2	3W-103111-S																	916			83			
3	3W-103111-N																	914			84			
4	3W-103111-W																	912			85			
5																								
6																								
7																								
8																								
9																								
10																								

Number of samples received: 4 (Additional samples shall be listed on attached long form.)

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative, I agree that submission of the following samples for requested analysis as indicated on this Chain of Custody shall constitute an analytical services agreement with payment terms of NET 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surcharge.

Relinquished By: <u>John P. [Signature]</u>	FedEx	Date/Time: <u>10/31/11</u>	Sample Condition: On Ice <u>   </u> Sealed <u>   </u> Intact <u>   </u>
Laboratory Use Only			Temp. (F°) <u>   </u> Yes / No <u>   </u> Yes / No <u>   </u> Yes / Ho <u>   </u>
Received By: <u>[Signature]</u>	Date/Time: <u>11-2-11</u>	Carrier: <u>FedEx</u>	
Results:	Contact	Phone Email Fax	Date Time Initials
	Contact	Phone Email Fax	Date Time Initials

Invoice # 7976 8079 8149



## Attachment I

Key to Count Sheets  
Count Sheets  
Analytical Procedures

Structures identifications consist of an Asbestos Type followed by a Structure Type

### Asbestos Type

A = Amosite  
An = Anthophyllite  
C = Chrysotile  
Cr = Crocidolite  
T = Tremolite

### Structure Types

F = Fiber  
B = Bundle  
C = Cluster  
M = Matrix

ND = no structures detected  
M = other structure associated with a matrix  
NAM = Non Asbestos Mineral  
XGB = partly obscured by a grid bar

### Sizing Conversion


1 length unit = 5 mm on screen = 0.278 micron  
1.80 length units = 0.5 micron  
18.0 length units = 5 microns

1 width unit = 1 mm on screen = 0.0556 micron

### TEM Analysts

Jeanne S. Orr  
Nathan DelHierro  
Angela Heitger  
Jonathan Bemard

Paul D. LoScalzo  
Mark Steiner  
Norberto Zimbleman  
Robert Workman



Upper and lower 95% confidence bounds for the number of structures counted assuming a Poisson distribution.

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 <del>NS</del> S
Voltage (KV)	100 KV
Magnification	<del>20KX</del> 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	917
Date received by lab	11/2/11
Lab Job Number:	223514
Lab Sample Number:	817.852

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	JB
Analysis date	11/3/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scooper Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	L5-1	ND												
	K5-1	ND					Prep A	60% ambient			5% debris			
	H5-1	ND					Prep B	80% ambient			5% debris			
	G5-1	ND												
B	K4-1	ND												
	H4-1	ND												
	G4-1	ND												
	F4-1	ND												

Rev 3-2009

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 <sup>(D)</sup> S
Voltage (KV)	100 KV
Magnification	<del>20KX</del> 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: tL =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	916
Date received by lab	11/2/11
Lab Job Number:	223514
Lab Sample Number:	817883

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	JB
Analysis date	11/3/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AA
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	H4-1	ND												
	G4-1	ND					Pap A	70% in dust			5-7% debris			
	F4-1	ND					Pap B	60% in dust			5-7% debris			
B	BF33	ND												
	G2-3	ND												
	F2-3	ND												
	E2-3	ND												
	C2-3	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 <u>N</u> S
Voltage (KV)	100 KV
Magnification	<u>20KX</u> 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 $\mu$ m
Scale: 1D =	0.056 $\mu$ m
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+K
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	914
Date received by lab	11/2/11
Lab Job Number:	223514
Lab Sample Number:	817.884

Analyzed by	JB
Analysis date	11/3/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AA
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	H3-6	ND												
	G3-6	ND												
	F3-6	ND												
	E3-6	ND												
B	H4-3	ND												
	G4-3	ND												
	F4-3	ND												
	E4-3	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 <u>NS</u>
Voltage (KV)	100 KV
Magnification	<u>20KX</u> 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.066 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	912
Date received by lab	11/2/11
Lab Job Number:	223514
Lab Sample Number:	817885

Analyzed by	JB
Analysis date	11/3/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	65-1	ND												
	F5-1	ND					Purp LAB	80% indirect			3-5% debris			
	E5-1	ND												
	C5-1	ND												
B	K3-3	ND												
	H5-3	ND												
	G5-3	ND												
	F5-3	ND												

Rev 3-2009

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

## Analytical Procedures – AHERA

Transmission electron microscopy/energy dispersive X-ray spectrometry/selected area electron diffraction (TEM/EDX/SAED) was employed in the analysis of the samples, which were collected on 25 mm mixed cellulose ester air filters. A portion of each filter was collapsed with acetone and etched in a plasma asher. The etched filter was then coated with a thin layer of carbon in a carbon side down. The sample was then placed inside a condensation washer and treated with acetone to remove the filter matrix and expose any inert material.

For each sample, enough grid openings on a 200 mesh TEM grid are analyzed to ensure an analytical sensitivity of at least 0.005 structures/cc. A minimum of four grid openings from two preparations are analyzed for each sample. The grid openings are searched for fibrous structures which, if present are analyzed by SAED and/or EDX (elemental analysis). The AHERA protocol requires SAED confirmation of enough chrysotile asbestos structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures). Both SAED and EDX confirmation are required of enough amphibole structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures) per sample. Either SAED or EDX is required for the remaining asbestos structures of either type. The morphology of each structure is determined and the length and the diameter of any asbestos structures are recorded. Asbestos fibers, bundles, cluster and matrices were identified and recorded. The asbestos structures have been defined in AHERA as follows:

<b>Fiber:</b>	is a structure having a minimum length greater than or equal to 0.5 micron with an aspect ratio of 5:1 or greater with substantially parallel sides.
<b>Bundle:</b>	is a structure composed of three or more fibers in parallel arrangement, with each fiber closer than the diameter of one fiber.
<b>Cluster:</b>	is a structure with fibers in random arrangements such that all fibers are intermixed and no single fiber is isolated from the group.
<b>Matrix:</b>	is a fiber or fibers with one end free and the other end embedded or hidden by a particulate. The exposed fiber end must meet the fiber definition given above.

If more than 50 asbestos structures are identified and confirmed on a sample, AHERA analysis may be terminated after completion of the grid opening, which contains the 50<sup>th</sup> structure. AHERA protocol requires the laboratory to reject any clearance sample which contains in excess of 25% total particulate loading or which appears to be unevenly loaded.

The AHERA protocol includes specific sampling requirements, including minimum numbers of samples and minimum air volumes. Specifically, the 70 structures/mm<sup>2</sup> clearance criteria is only allowed for sets five inside samples (collected in a group of 13 samples including: five outsides and three blanks) with volumes greater than 1200 liters (40.CFR Part 763, page 41894). Deviation from the AHERA sampling protocol may affect the validity of the analytical results. Analysis of samples collected by non-protocol methods are not accredited by NVLAP

### Equations Used for Calculations

$$\text{Area Analyzed, mm}^2 = \# \text{ GO counted} \times \text{Average GO Area (mm)}$$

$$\text{Concentration, s/cc} = \frac{\# \text{ Asbestos Structures}}{\# \text{ GO Counted}} \times \frac{1}{\text{Volume (L)}} \times \frac{\text{Eff. Filter Area (mm}^2\text{)}}{\text{Average GO area (mm}^2\text{)}} \times \frac{\text{IL}}{1000\text{cc}}$$

$$\text{Filter loading, s/mm}^2 = \frac{\# \text{ Asbestos structures}}{\text{Area Analyzed (mm}^2\text{)}}$$

GO = TEM grid opening



November 7, 2011

Laboratory Code: RES  
Subcontract Number: NA  
Laboratory Report: RES 223662-1  
Project # / P.O. #: None Given  
Project Description: 3rd West Sub Station - RMP

Eldon Romney  
R & R Environmental  
47 West 9000 South #2  
Sandy UT 84070

Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

RES 223662-1 is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,

A handwritten signature in black ink, appearing to read "Jeanne Orr", is written over a horizontal line.

Jeanne Spencer Orr  
President

# RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0; TDH: #30-0018

TABLE I. TEM AIR FILTER SAMPLE DATA AND ANALYTICAL RESULTS

RES Job Number: RES 223662-1  
 Client: R & R Environmental  
 Client Project Number / P.O.: None Given  
 Client Project Description: 3rd West Sub Station - RMP  
 Date Samples Received: November 4, 2011  
 Analysis Type: TEM, AHERA  
 Turnaround: 24 Hour  
 Date Samples Analyzed: November 4, 2011

Client ID Number	Lab ID Number	Area Analyzed	Air Volume Sampled	Number of Asbestos Structures Detected	Analytical Sensitivity	Asbestos Concentration	Filter Loading
		(mm <sup>2</sup> )	(L)		(s/cc)	(s/cc)	(s/mm <sup>2</sup> )
3W-110211-E	EM 819163	0.1100	1001	ND	0.0035	BAS	BAS
3W-110211-S	EM 819164	0.1100	999	ND	0.0035	BAS	BAS
3W-110211-N	EM 819165	0.1100	997	ND	0.0035	BAS	BAS
3W-110211-W	EM 819166	0.1100	997	ND	0.0035	BAS	BAS

NA = Not Analyzed  
 ND = None Detected  
 BAS = Below Analytical Sensitivity  
 Average Grid Opening in mm<sup>2</sup> = 0.011

Filter Material = Mixed Cellulose Ester  
 Filter Diameter = 25 mm  
 Effective Filter Area = 385 sq mm

Digitally signed  
 by Gina  
 Vetrano  
 Date  
 2011.11.07  
 09:32:59 -0700

DATA QA



Due Date: 11/11/11  
Due Time: 8:30a

RES 223662

**REI LAB Reservoirs Environmental, Inc.**

5801 Logan St. Denver, CO 80216 • Ph: 303 964-1986 • Fax 303-477-4276 • Toll Free 866 RESI-ENV

Pager : 303-809-8088

**INVOICE TO: (IF DIFFERENT)**

**CONTACT INFORMATION:**

Company: <u>P.R. Environmental</u>	Company:	Contact: <u>Dave Roskelley</u>	Contact:
Address: <u>412W 9800S.</u>	Address:	Phone:	Phone:
<u>Sandy, UT. 84070</u>		Fax:	Fax:
		Cell/pager: <u>801 541-1035</u>	Cell/pager:
Project Number and/or P.O. #:		Final Data Deliverable Email Address:	
Project Description/Location: <u>3rd West Sub Station - RMP</u>		<u>dave@renviro.com</u>	

ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm		REQUESTED ANALYSIS												VALID MATRIX CODES		LAB NOTES:							
PLM / PCM / TEM <u>   </u> RUSH (Same Day) <u>X</u> PRIORITY (Next Day) <u>   </u> STANDARD (Rush PCM = 2hr, TEM = 6hr.)		PLM - Short report, Point Count	TEM - AHERA, Level II, 7402, ISO, +/-, Quant, Semi-quant, Micro-vac, ISO-Indirect Preps	PCM - 7400A, 7400B, OSHA	DUST - Total, Respirable	METALS - Analytes(s)	RCRA 8, TCLP, Welding Fume, Metals Scan	ORGANICS - METH	Salmonella: +/-	E.coli O157:H7: +/-	Listeria: +/-	Aerobic Plate Count: +/- or Quantification	E.coli: +/- or Quantification	Coliforms: +/- or Quantification	S.aureus: +/- or Quantification	Y & M: +/- or Quantification	Mold: +/-, Identification, Quantification	SAMPLES INITIALS OR OTHER NOTES	Air = A	Bulk = B			
CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm																			Dust = D	Paint = P			
Metal(s) / Dust <u>   </u> RUSH <u>   </u> 24 hr. <u>   </u> 3-5 Day																			Soil = S	Wipe = W			
RCRA 8 / Metals & Welding <u>   </u> RUSH <u>   </u> 5 day <u>   </u> 10 day																			Swab = SW	F = Food			
Fume Scan / TCLP <u>   </u> RUSH <u>   </u> 5 day <u>   </u> 10 day																			Drinking Water = DW	Waste Water = WW			
Organics <u>   </u> 24 hr. <u>   </u> 3 day <u>   </u> 5 Day																			O = Other				
MICROBIOLOGY LABORATORY HOURS: Weekdays: 8am - 5pm																			**ASTM E1792 approved wipe media only**				
E.coli O157:H7, Coliforms, S.aureus <u>   </u> 24 hr. <u>   </u> 2 Day <u>   </u> 3-5 Day																		Sample Volume (L) / Area	Matrix Code	# Containers	Date Collected mm/dd/yy	Time Collected hh:mm s/p	EM Number (Laboratory Use Only)
Salmonella, Listeria, E.coli, APC, Y & M <u>   </u> 48 Hr. <u>   </u> 3-5 Day																							
Mold <u>   </u> RUSH <u>   </u> 24 Hr <u>   </u> 48 Hr <u>   </u> 5 Day <u>   </u> 5 Day																							
**Turnaround times establish a laboratory priority, subject to laboratory volume and are not guaranteed. Additional fees apply for afterhours, weekends and holidays.**																							
Special Instructions:																							
Client sample ID number (Sample ID's must be Unique)																							
1	3W-110211-E		X															1001	A		11/02/11		89163
2	3W-110211-S																	999					64
3	3W-110211-N																	997					65
4	3W-110211-W																	997					66
5																							
6																							
7																							
8																							
9																							
10																							

Number of samples received: 4 (Additional samples shall be listed on attached long form.)

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested analysis as indicated on this Chain of Custody shall constitute an analytical services agreement with payment terms of NET 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surcharge.

Relinquished By: <u>[Signature]</u>	Date/Time: <u>11/02/11</u>	Sample Condition: <u>On Ice</u>	On Ice: <u>Yes</u>	Sealed: <u>Yes</u>	Intact: <u>Yes</u>
Laboratory Use Only		Temp. (F°): <u>   </u>	Yes / No: <u>   </u>	Yes / No: <u>   </u>	Yes / No: <u>   </u>
Received By: <u>[Signature]</u>	Date/Time: <u>11/4/11</u>	Carrier: <u>FedEx</u>			
Results:	Contact: <u>Dave</u>	Phone: <u>   </u> Email: <u>   </u> Fax: <u>   </u>	Date: <u>11/4/11</u>	Time: <u>7:30p</u>	Initials: <u>[Signature]</u>
	Contact: <u>   </u>	Phone: <u>   </u> Email: <u>   </u> Fax: <u>   </u>	Date: <u>   </u>	Time: <u>   </u>	Initials: <u>   </u>

Invoice # 7970 9067 7594

## Attachment I

Key to Count Sheets  
Count Sheets  
Analytical Procedures

Structures identifications consist of an Asbestos Type followed by a Structure Type

### Asbestos Type

A = Amosite  
An = Anthophyllite  
C = Chrysotile  
Cr = Crocidolite  
T = Tremolite

### Structure Types

F = Fiber  
B = Bundle  
C = Cluster  
M = Matrix

ND = no structures detected  
M = other structure associated with a matrix  
NAM = Non Asbestos Mineral  
XGB = partly obscured by a grid bar

### Sizing Conversion


1 length unit = 5 mm on screen = 0.278 micron  
1.80 length units = 0.5 micron  
18.0 length units = 5 microns

1 width unit = 1 mm on screen = 0.0556 micron

### TEM Analysts

Jeanne S. Orr  
Nathan DelHiero  
Angela Heitger  
Jonathan Bernard

Paul D. LoScalzo  
Mark Steiner  
Norberto Zimbleman  
Robert Workman



Upper and lower 95% confidence bounds for the number of structures counted assuming a Poisson distribution.

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N(S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	NA
QA Type	No OA

Client :	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	1001
Date received by lab	11-4-11
Lab Job Number:	223662
Lab Sample Number:	819163

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-4-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	D	NAM		Sketch	Photo	EOS
A	H5-3	ND												
	G5-6	ND												
	G5-3	ND												
	F5-6	ND												
B	L5-3	ND												
	K5-6	ND												
	K5-3	ND												
	H5-6	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

T:\QAQC\Lab\General Lab Documents\TEM Count Sheet rev.1-11.xls

Reservoir Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.066 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	NA
QA Type	NO QA

Client:	R + R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	999
Date received by lab	11-4-11
Lab Job Number	223662
Lab Sample Number:	819164

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	MK
Analysis date	11/4/11
Method (D=Direct, I=Indirect)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	ES-34	ND												
	CS-34	ND					Prep A	80% intact		nsf. debris				
	B5-34	ND					Prep B	~50% intact		nsf. debris				
	E4-1	ND									See prep 11/4/11			
B	K6-4	ND												
	H6-4	ND												
	G7-1	ND												
	G5-4	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

T:\QAQC\Lab\General Lab Documents\TEM Count Sheet rev.1-11.xls

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 10 =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	NA
QA Type	no QA

Client:	R + R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	997
Date received by lab	11-4-11
Lab Job Number:	223662
Lab Sample Number:	819165

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	RL
Analysis date	11/4/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting miles (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	K4-1	ND												
	H4-1	ND					Prep A 70% intact			15% debris				
	G4-1	ND					Prep B ~60% intact			5% debris				
	F4-1	ND								Temp/mon 11/4/11				
B	C5-4	ND												
	C5-6	ND												
	G5-3	ND												
	G6-6	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	(20KX) 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	NH
QA Type	W OA

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	997
Date received by lab	11-4-11
Lab Job Number:	223662
Lab Sample Number:	819166

Analyzed by	M
Analysis date	11/4/11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	G6-3	ND												
	F6-3	ND					Prep A	70% mineral		3-5% debris				
	E6-3	ND					Prep B	~ A						
	C6-3	ND								per Kim 11/4/11				
B	F5-4	ND												
	E5-4	ND												
	F3-1	ND												
	E3-1	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

## Analytical Procedures – AHERA

Transmission electron microscopy/energy dispersive X-ray spectrometry/selected area electron diffraction (TEM/EDX/SAED) was employed in the analysis of the samples, which were collected on 25 mm mixed cellulose ester air filters. A portion of each filter was collapsed with acetone and etched in a plasma asher. The etched filter was then coated with a thin layer of carbon in a carbon side down. The sample was then placed inside a condensation washer and treated with acetone to remove the filter matrix and expose any inert material.

For each sample, enough grid openings on a 200 mesh TEM grid are analyzed to ensure an analytical sensitivity of at least 0.005 structures/cc. A minimum of four grid openings from two preparations are analyzed for each sample. The grid openings are searched for fibrous structures which, if present are analyzed by SAED and/or EDX (elemental analysis). The AHERA protocol requires SAED confirmation of enough chrysotile asbestos structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures). Both SAED and EDX confirmation are required of enough amphibole structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures) per sample. Either SAED or EDX is required for the remaining asbestos structures of either type. The morphology of each structure is determined and the length and the diameter of any asbestos structures are recorded. Asbestos fibers, bundles, cluster and matrices were identified and recorded. The asbestos structures have been defined in AHERA as follows:

<b>Fiber:</b>	is a structure having a minimum length greater than or equal to 0.5 micron with an aspect ratio of 5:1 or greater with substantially parallel sides.
<b>Bundle:</b>	is a structure composed of three or more fibers in parallel arrangement, with each fiber closer than the diameter of one fiber.
<b>Cluster:</b>	is a structure with fibers in random arrangements such that all fibers are intermixed and no single fiber is isolated from the group.
<b>Matrix:</b>	is a fiber or fibers with one end free and the other end embedded or hidden by a particulate. The exposed fiber end must meet the fiber definition given above.

If more than 50 asbestos structures are identified and confirmed on a sample, AHERA analysis may be terminated after completion of the grid opening, which contains the 50<sup>th</sup> structure. AHERA protocol requires the laboratory to reject any clearance sample which contains in excess of 25% total particulate loading or which appears to be unevenly loaded.

The AHERA protocol includes specific sampling requirements, including minimum numbers of samples and minimum air volumes. Specifically, the 70 structures/mm<sup>2</sup> clearance criteria is only allowed for sets five inside samples (collected in a group of 13 samples including: five outsides and three blanks) with volumes greater than 1200 liters (40 CFR Part 763, page 41894). Deviation from the AHERA sampling protocol may affect the validity of the analytical results. Analysis of samples collected by non-protocol methods are not accredited by NVLAP

### Equations Used for Calculations

$$\text{Area Analyzed, mm}^2 = \# \text{ GO counted} \times \text{Average GO Area (mm)}$$

$$\text{Concentration, S/cc} = \frac{\# \text{ Asbestos Structures}}{\# \text{ GO Counted}} \times \frac{1}{\text{Volume (L)}} \times \frac{\text{Eff. Filter Area (mm}^2\text{)}}{\text{Average GO area (mm}^2\text{)}} \times \frac{1\text{L}}{1000\text{cc}}$$

$$\text{Filter loading, S/mm}^2 = \frac{\# \text{ Asbestos structures}}{\text{Area Analyzed (mm}^2\text{)}}$$

$$\text{GO} = \text{TEM grid opening}$$

Due Date: 11/8/11  
Due Time: 9:45am

**REILAB** **Reservoirs Environmental, Inc.**  
5801 Logan St. Denver, CO 80216 • Ph: 303 984-1888 • Fax 303-477-4278 • Toll Free: 888 PESI-ENV  
Pager: 303-509-2088

RES 223762

Page 1 of 1

**INVOICE TO: (IF DIFFERENT)**

**CONTACT INFORMATION:**

Company: <u>REILAB Environmental</u>	Company:	Contact: <u>Dave Roskelley</u>	Contact:
Address:	Address:	Phone:	Phone:
		Fax:	Fax:
		Cell/pager: <u>801 541-1035</u>	Cell/pager:
Project Number and/or P.O. #:		Final Data Deliverable Email Address:	
Project Description/Location: <u>3rd West Sub Station RMP</u>			

ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm		REQUESTED ANALYSIS												VALID MATRIX CODES				LAB NOTES:			
PLM / PCM / TEM	RUSH (Same Day) <u>X</u> PRIORITY (Next Day) STANDARD													Air = A	Bulk = B	<u>10</u> <u>10</u>					
(Rush PCM = 2hr, TEM = 8hr.)														Dust = D	Paint = P						
CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm														Soil = S	Wipe = W						
Metal(s) / Dust	RUSH 24 hr. 3-5 Day													Swab = SW	F = Food						
RCRA 8 / Metals A Welding	RUSH 5 day 10 day													Drinking Water = DW	Waste Water = WW						
Fume Scan / TCLP														O = Other							
Organics	24 hr. 3 day 5 Day													**ASTM E 1762 approved wipe media only**							
MICROBIOLOGY LABORATORY HOURS: Weekdays: 9am - 5pm														Sample Volume (L) / Area	Matrix Code	# Containers	Date Collected m/d/y	Time Collected h/m a/p	EM Number (Laboratory Use Only)		
E.coli O157:H7, Coliforms, S.aureus	24 hr. 2 Day 3-5 Day	PLM - Short report, Long report, Point Count	TEM - AHERA, Level II, 7402, ISO, +/-, Quant, Semi-quant, Micro-vec, ISO-indirect Preps	PCM - 7400A, 7400B, OSHA	DUST - Total, Respirable	METALS - Analysis	RCRA 8, TCLP, Welding Fume, Metals Scan	ORGANICS - METH	Salmonella: +/-	E.coli O157:H7: +/-	Listeria: +/-	Aerobic Plate Count: +/- or Quantification	E.coli +/- or Quantification	Coliforms: +/- or Quantification	S.aureus: +/- or Quantification	Y & M: +/- or Quantification	Mold: +/- Identification, Quantification				
Salmonella, Listeria, E.coli, APC, Y & M	48 Hr. 3-6 Day													MICROBIOLOGY							
Mold	RUSH 24 Hr 48 Hr 3 Day 5 Day													SAMPLER'S INITIALS OR OTHER NOTES							
**Turnaround times establish a laboratory priority, subject to laboratory volume and are not guaranteed. Additional fees apply for afterhours, weekends and holidays.**																					
Special Instructions:																					
Client sample ID number (Sample ID's must be unique)																					
1	3W110411-E																		819882		
2	3W110411-S																		83		
3	3W110411-N Blank																		84		
4	3W110411-W																		85		
5																					
6																					
7																					
8																					
9																					
10																					

Number of samples received: 4 (Additional samples shall be listed on attached long form.)

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculation resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested analysis as indicated on this Chain of Quality shall constitute an analytical services agreement with payment terms of NET 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surcharge.

Relinquished By: <u>Justin Kyrie</u>	Date/Time: <u>11/04/11</u>	Sample Condition:	On Ice	Sealed	Intact			
Laboratory Use Only		Temp. (F°)	Yes / No	Yes / No	Yes / No			
Received By: <u>Dave</u>	Date/Time: <u>11/7/11</u> <u>9:45a</u>	Carrier: <u>FedEx</u>						
Results:	Contact: <u>Dave</u> Phone: <u>303-509-2088</u> Email: <u>dave@reilab.com</u> Fax: <u>303-477-4278</u>	Date: <u>11/8</u>	Time: <u>9A</u>	Initials: <u>DR</u>	Contact: <u>Dave</u> Phone: <u>303-509-2088</u> Email: <u>dave@reilab.com</u> Fax: <u>303-477-4278</u>	Date: <u>11/9</u>	Time: <u>7:32a</u>	Initials: <u>DR</u>

FL # 7477 0628 9293  
MSK



## Attachment I

### Key to Count Sheets Count Sheets Analytical Procedures

Structures identifications consist of an Asbestos Type followed by a Structure Type

#### Asbestos Type

A = Amosite  
An = Anthophyllite  
C = Chrysotile  
Cr = Crocidolite  
T = Tremolite

#### Structure Types

F = Fiber  
B = Bundle  
C = Cluster  
M = Matrix

ND = no structures detected  
M = other structure associated with a matrix  
NAM = Non Asbestos Mineral  
XGB = partly obscured by a grid bar

#### Sizing Conversion


1 length unit = 5 mm on screen = 0.278 micron  
1.80 length units = 0.5 micron  
18.0 length units = 5 microns

1 width unit = 1 mm on screen = 0.0556 micron

#### TEM Analysts

Jeanne S. Orr  
Nathan DelHiero  
Angela Heitger  
Jonathan Bemard

Paul D. LoScalzo  
Mark Steiner  
Norberto Zimbleman  
Robert Workman



Upper and lower 95% confidence bounds for the number of structures counted assuming a Poisson distribution.

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R & R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	1018
Date received by lab	11-7-11
Lab Job Number:	223762
Lab Sample Number:	819882

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-7-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Data at JB uplu

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	F4-1	ND												
	E4-4	ND												
	E4-1	ND												
	C4-4	ND												
B	G5-4	ND												
	F5-4	ND												
	G5-1	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	20RX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Tyoe	

Client :	R & R
Sample Tyoe (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	241
Date received by lab	11-7-11
Lab Job Number:	223762
Lab Sample Number:	819883

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-7-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibola	C	NAM		Sketch	Photo	EDS
A	F4-6	ND												
	F4-3	ND												
	E4-6	ND												
	E4-3	ND												
	C4-6	ND												
B	H4-1	ND												
	G4-4	ND												
	G4-1	ND												
	F4-4	ND												
	F4-1	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N(S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	973
Date received by lab	11-7-11
Lab Job Number	223762
Lab Sample Number:	819885

Analyzed by	AH
Analysis date	11-7-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grkl storage location	Month Analyzed
Scope Alignment	Date Analyzed

## F-Factor Calculation (indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Wkth		Amphibole	C	NAM		Sketch	Photo	EDS
A	F4-4	MD												
	F4-1	MD												
	E4-4	MD												
	E4-1	MD												
3	C4-4	MD												
	C4-1	MD												
	B4-4	MD												
	B4-1	MD												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

## Analytical Procedures – AHERA

Transmission electron microscopy/energy dispersive X-ray spectrometry/selected area electron diffraction (TEM/EDX/SAED) was employed in the analysis of the samples, which were collected on 25 mm mixed cellulose ester air filters. A portion of each filter was collapsed with acetone and etched in a plasma asher. The etched filter was then coated with a thin layer of carbon in a carbon side down. The sample was then placed inside a condensation washer and treated with acetone to remove the filter matrix and expose any inert material.

For each sample, enough grid openings on a 200 mesh TEM grid are analyzed to ensure an analytical sensitivity of at least 0.005 structures/cc. A minimum of four grid openings from two preparations are analyzed for each sample. The grid openings are searched for fibrous structures which, if present are analyzed by SAED and/or EDX (elemental analysis). The AHERA protocol requires SAED confirmation of enough chrysotile asbestos structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures). Both SAED and EDX confirmation are required of enough amphibole structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures) per sample. Either SAED or EDX is required for the remaining asbestos structures of either type. The morphology of each structure is determined and the length and the diameter of any asbestos structures are recorded. Asbestos fibers, bundles, cluster and matrices were identified and recorded. The asbestos structures have been defined in AHERA as follows:

<b>Fiber:</b>	is a structure having a minimum length greater than or equal to 0.5 micron with an aspect ratio of 5:1 or greater with substantially parallel sides.
<b>Bundle:</b>	is a structure composed of three or more fibers in parallel arrangement, with each fiber closer than the diameter of one fiber.
<b>Cluster:</b>	is a structure with fibers in random arrangements such that all fibers are intermixed and no single fiber is isolated from the group.
<b>Matrix:</b>	is a fiber or fibers with one end free and the other end embedded or hidden by a particulate. The exposed fiber end must meet the fiber definition given above.

If more than 50 asbestos structures are identified and confirmed on a sample, AHERA analysis may be terminated after completion of the grid opening, which contains the 50<sup>th</sup> structure. AHERA protocol requires the laboratory to reject any clearance sample which contains in excess of 25% total particulate loading or which appears to be unevenly loaded.

The AHERA protocol includes specific sampling requirements, including minimum numbers of samples and minimum air volumes. Specifically, the 70 structures/mm<sup>2</sup> clearance criteria is only allowed for sets five inside samples (collected in a group of 13 samples including: five outsides and three blanks) with volumes greater than 1200 liters (40 CFR Part 763, page 41894). Deviation from the AHERA sampling protocol may affect the validity of the analytical results. Analysis of samples collected by non-protocol methods are not accredited by NVLAP

### Equations Used for Calculations

$$\text{Area Analyzed, mm}^2 = \# \text{ GO counted} \times \text{Average GO Area (mm)}$$

$$\text{Concentration, s/cc} = \frac{\# \text{ Asbestos Structures}}{\# \text{ GO Counted}} \times \frac{1}{\text{Volume (L)}} \times \frac{\text{Eff. Filter Area (mm}^2\text{)}}{\text{Average GO area (mm}^2\text{)}} \times \frac{1\text{L}}{1000\text{cc}}$$

$$\text{Filter loading, s/mm}^2 = \frac{\# \text{ Asbestos structures}}{\text{Area Analyzed (mm}^2\text{)}}$$

GO = TEM grid opening

**REI LAB** ***Reservoirs Environmental, Inc.***

November 9, 2011

Laboratory Code: RES  
Subcontract Number: NA  
Laboratory Report: RES 223763-1  
Project # / P.O. #: None Given  
Project Description: 3rd West Sub Station  
RMP

David Roskelley  
R & R Environmental  
47 West 9000 South #2  
Sandy UT 84070


Dear Customer,

Reservoirs Environmental, Inc. is an analytical laboratory accredited for the analysis of Industrial Hygiene and Environmental matrices by the National Voluntary Laboratory Accreditation Program (NVLAP), Lab Code 101896-0 for Transmission Electron Microscopy (TEM) and Polarized Light Microscopy (PLM) analysis and the American Industrial Hygiene Association (AIHA), Lab ID 101533 - Accreditation Certificate #480 for Phase Contrast Microscopy (PCM) analysis. This laboratory is currently proficient in both Proficiency Testing and PAT programs respectively.

Reservoirs Environmental, Inc. has analyzed the following samples for asbestos content as per your request. The analysis has been completed in general accordance with the appropriate methodology as stated in the attached analysis table. The results have been submitted to your office.

RES 223763-1 is the job number assigned to this study. This report is considered highly confidential and the sole property of the customer. Reservoirs Environmental, Inc. will not discuss any part of this study with personnel other than those of the client. The results described in this report only apply to the samples analyzed. This report must not be used to claim endorsement of products or analytical results by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without written approval from Reservoirs Environmental, Inc. Samples will be disposed of after sixty days unless longer storage is requested. If you have any questions about this report, please feel free to call 303-964-1986.

Sincerely,



Jeanne Spencer Orr  
President

# RESERVOIRS ENVIRONMENTAL, INC.

NVLAP Lab Code 101896-0; TDH: #30-0015

**TABLE I. TEM AIR FILTER SAMPLE DATA AND ANALYTICAL RESULTS**

**RES Job Number:** RES 223763-1  
**Client:** R & R Environmental  
**Client Project Number / P.O.:** None Given  
**Client Project Description:** 3rd West Sub Station RMP  
**Date Samples Received:** November 7, 2011  
**Analysis Type:** TEM, AHERA  
**Turnaround:** 24 Hour  
**Date Samples Analyzed:** November 7 & 8, 2011

Client ID Number	Lab ID Number	Area Analyzed	Air Volume Sampled	Number of Asbestos Structures Detected	Analytical Sensitivity	Asbestos Concentration	Filter Loading
		(mm <sup>2</sup> )	(L)		(s/cc)	(s/cc)	(s/mm <sup>2</sup> )
3W-110311-E	EM 819879	0.0770	1117	ND	0.0045	BAS	BAS
3W-110311-S	EM 819880	0.0770	1110	ND	0.0045	BAS	BAS
3W-110311-W	EM 819881	0.0770	1109	ND	0.0045	BAS	BAS

NA = Not Analyzed

ND = None Detected


BAS = Below Analytical Sensitivity

Average Grid Opening in mm<sup>2</sup> = 0.011

Filter Material = Mixed Cellulose Ester

Filter Diameter = 25 mm

Effective Filter Area = 385 sq mm

  
 Digitally  
 signed by  
 Gina Vetrano  
 Date:  
 2011.11.09  
 07:49:41 -  
 0700'

**DATA QA**

Due Date: 11-8-11  
Due Time: 9:00am

**REI LAB Reservoirs Environmental, Inc.**  
501 Logan St. Denver, CO 80216 • Ph: 303-664-1966 • Fax 303-477-4275 • Toll Free: 866-REI-ENV  
Pager: 303-606-2088

RES 223763

Page 1 of 1

INVOICE TO: (IF DIFFERENT)

CONTACT INFORMATION:

Company: RFR Environmental	Company:	Contact: Dave Roskelley	Contact:
Address: 47 W 9800 S	Address:	Phone:	Phone:
16th St. #4070		Fax:	Fax:
		Cell/pager: 801-541-1035	Cell/pager:
Project Number and/or P.O. #:		Final Data Deliverable Email Address:	
Project Description/Location: 300 West Sub Station RAMP		dave@reimv.com	

ASBESTOS LABORATORY HOURS: Weekdays: 7am - 7pm		REQUESTED ANALYSIS										VALID MATRIX CODES		LAB NOTES:				
PLM / PCM / TEM	RUSH (Same Day) <input type="checkbox"/> PRIORITY (Next Day) <input checked="" type="checkbox"/> STANDARD	PLM	TEM	PCM	DUST	METALS	RCRA 8	ORGANICS	MICROBIOLOGY	SAMPLERS INITIALS OR OTHER NOTES	Sample Volume (L) / Area	Matrix Code	# Containers	Date Collected m/d/yyyy	Time Collected hh:mm a/p	EM Number (Laboratory Use Only)		
CHEMISTRY LABORATORY HOURS: Weekdays: 8am - 5pm																		
Metal(s) / Dust	RUSH 24 hr. 3-5 Day																	
RCRA 8 / Metals & Welding	RUSH 5 day 10 day																	
Fume Seal / TCLP																		
Organics	24 hr. 5 day 5 Day																	
MICROBIOLOGY LABORATORY HOURS: Weekdays: 9am - 6pm																		
E.coli O157:H7, Coliforms, S.aureus	24 hr. 2 Day 3-5 Day																	
Salmonella, Listeria, E.coli, APC, Y & M	48 Hr. 3-5 Day																	
Mold	RUSH 24 Hr 46 Hr 3 Day 5 Day																	
**Turnaround times establish a laboratory priority, subject to laboratory volume and are not guaranteed. Additional fees apply for afterhours, weekends and holidays.**																		
Special Instructions:																		
Client sample ID number (Sample ID's must be unique)																		
1 3W 110311-E																		
2 3W 110311-S																		
3 3W 110311-W																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		

Number of samples received: 3 (Additional samples shall be listed on attached long form.)

NOTE: REI will analyze incoming samples based upon information received and will not be responsible for errors or omissions in calculations resulting from the inaccuracy of original data. By signing client/company representative agrees that submission of the following samples for requested analysis as indicated on this Chain of Custody shall constitute an analytical services agreement with payment terms of NET 30 days, failure to comply with payment terms may result in a 1.5% monthly interest surcharge.

Relinquished By: [Signature]	Date/Time: 11/3/11	Sample Condition: On Ice Sealed Intact
Laboratory Use Only		Temp. (F°) Yes / No Yes / No Yes / No
Received By: [Signature]	Date/Time: 11-7-11 @ 2:40pm	Carrier: FedEx
Results:	Contact Dave Phone Email Fax Date 11-8-11 Time 9:00 Initials AW	Contact Phone Email Fax Date 11-8-11 Time 7:45 Initials C
	Contact Phone Email Fax Date Time Initials	Contact Phone Email Fax Date Time Initials

Tracy #. 7983 757 6683



## Attachment I

Key to Count Sheets  
Count Sheets  
Analytical Procedures

Structures identifications consist of an Asbestos Type followed by a Structure Type

### Asbestos Type

A = Amosite  
An = Anthophyllite  
C = Chrysotile  
Cr = Crocidolite  
T = Tremolite

### Structure Types

F = Fiber  
B = Bundle  
C = Cluster  
M = Matrix

ND = no structures detected  
M = other structure associated with a matrix  
NAM = Non Asbestos Mineral  
XGB = partly obscured by a grid bar

### Sizing Conversion


1 length unit = 5 mm on screen = 0.278 micron  
1.80 length units = 0.5 micron  
18.0 length units = 5 microns

1 width unit = 1 mm on screen = 0.0556 micron

### TEM Analysts

Jeanne S. Orr  
Nathan DelHiero  
Angela Heitger  
Jonathan Bemard

Paul D. LoScalzo  
Mark Steiner  
Norberto Zimbleman  
Robert Workman



Upper and lower 95% confidence bounds for the number of structures counted assuming a Poisson distribution.

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	20KX 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	1110
Date received by lab	11-7-11
Lab Job Number	223763
Lab Sample Number	819880

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-7-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	F6-6	ND												
	F6-3	ND												
	E6-6	ND												
	E6-3	ND												
3	E4-4	ND												
	E4-1	ND												
	C4-4	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	(20KX) 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	1117
Date received by lab	11-7-11
Lab Job Number:	223763
Lab Sample Number:	819879

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter Used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-7-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Data Qd  
JB 11/8/11

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	F5-4	ND												
	F5-1	ND												
	E5-4	ND												
	E5-1	ND												
B	G4-1	ND												
	F4-4	ND												
	F4-1	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

Reservoirs Environmental, Inc.  
TEM Asbestos Structure Count

Laboratory name:	REI
Instrument	JEOL 100 CX N (S)
Voltage (KV)	100 KV
Magnification	(20KX) 10KX
Grid opening area (mm <sup>2</sup> )	0.011
Scale: 1L =	0.28 um
Scale: 1D =	0.056 um
Primary filter area (mm <sup>2</sup> )	385
Secondary Filter Area (mm <sup>2</sup> )	
QA Type	

Client:	R+R
Sample Type (A=Air, D=Dust):	A
Air volume (L) or dust area (cm <sup>2</sup> )	1109
Date received by lab	11-7-11
Lab Job Number:	223763
Lab Sample Number:	819881

## F-Factor Calculation (Indirect Preps Only):

Fraction of primary filter used	
Total Resuspension Volume (ml)	
Volume Applied to secondary filter (ml)	

Analyzed by	AH
Analysis date	11-8-11
Method (D=Direct, I=Indirect, IA=Indirect, ashed)	D
Counting rules (ISO, AHERA, ASTM)	AH
Grid storage location	Month Analyzed
Scope Alignment	Date Analyzed

Grid	Grid Opening	Structure Type	No. of Structures		Dimensions		Identification	Mineral Class			Sketch/Comments	1 = yes, blank = no		
			Primary	Total	Length	Width		Amphibole	C	NAM		Sketch	Photo	EDS
A	E4-6	ND												
	E4-3	ND												
	C4-6	ND												
	C4-3	ND												
B	G3-6	ND												
	G3-3	ND												
	F3-6	ND												

LA = Libby-type amphibole

OA = Other (non-Libby type) amphibole

C = Chrysotile

NAM = Non-asbestos material

## Analytical Procedures – AHERA

Transmission electron microscopy/energy dispersive X-ray spectrometry/selected area electron diffraction (TEM/EDX/SAED) was employed in the analysis of the samples, which were collected on 25 mm mixed cellulose ester air filters. A portion of each filter was collapsed with acetone and etched in a plasma asher. The etched filter was then coated with a thin layer of carbon in a carbon side down. The sample was then placed inside a condensation washer and treated with acetone to remove the filter matrix and expose any inert material.

For each sample, enough grid openings on a 200 mesh TEM grid are analyzed to ensure an analytical sensitivity of at least 0.005 structures/cc. A minimum of four grid openings from two preparations are analyzed for each sample. The grid openings are searched for fibrous structures which, if present are analyzed by SAED and/or EDX (elemental analysis). The AHERA protocol requires SAED confirmation of enough chrysotile asbestos structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures). Both SAED and EDX confirmation are required of enough amphibole structures on each sample to cause the sample to exceed 70 structures/mm<sup>2</sup> (usually 4 or 5 structures) per sample. Either SAED or EDX is required for the remaining asbestos structures of either type. The morphology of each structure is determined and the length and the diameter of any asbestos structures are recorded. Asbestos fibers, bundles, cluster and matrices were identified and recorded. The asbestos structures have been defined in AHERA as follows:

- Fiber:** is a structure having a minimum length greater than or equal to 0.5 micron with an aspect ratio of 5:1 or greater with substantially parallel sides.
- Bundle:** is a structure composed of three or more fibers in parallel arrangement, with each fiber closer than the diameter of one fiber.
- Cluster:** is a structure with fibers in random arrangements such that all fibers are intermixed and no single fiber is isolated from the group.
- Matrix:** is a fiber or fibers with one end free and the other end embedded or hidden by a particulate. The exposed fiber end must meet the fiber definition given above.

If more than 50 asbestos structures are identified and confirmed on a sample, AHERA analysis may be terminated after completion of the grid opening, which contains the 50<sup>th</sup> structure. AHERA protocol requires the laboratory to reject any clearance sample which contains in excess of 25% total particulate loading or which appears to be unevenly loaded.

The AHERA protocol includes specific sampling requirements, including minimum numbers of samples and minimum air volumes. Specifically, the 70 structures/mm<sup>2</sup> clearance criteria is only allowed for sets five inside samples (collected in a group of 13 samples including: five outsides and three blanks) with volumes greater than 1200 liters (40 CFR Part 763, page 41894). Deviation from the AHERA sampling protocol may affect the validity of the analytical results. Analysis of samples collected by non-protocol methods are not accredited by NVLAP

### Equations Used for Calculations

$$\text{Area Analyzed, mm}^2 = \# \text{ GO counted} \times \text{Average GO Area (mm)}$$

$$\text{Concentration, s/cc} = \frac{\# \text{ Asbestos Structures}}{\# \text{ GO Counted}} \times \frac{1}{\text{Volume (L)}} \times \frac{\text{Eff. Filter Area (mm}^2\text{)}}{\text{Average GO area (mm}^2\text{)}} \times \frac{1 \text{ L}}{1000 \text{ cc}}$$

$$\text{Filter loading, s/mm}^2 = \frac{\# \text{ Asbestos structures}}{\text{Area Analyzed (mm}^2\text{)}}$$

GO = TEM grid opening